



2-6-2020

Lake Whatcom Monitoring Project 2018/2019 Report

Robin A. Matthews

Western Washington University, robin.matthews@wwu.edu

Angela Lee Strecker

Western Washington University

Michael Hilles

Western Washington University

Joan Pickens

Western Washington University

Robert J. Mitchell

Western Washington University

See next page for additional authors

Follow this and additional works at: https://cedar.wwu.edu/lakewhat_annualreps



Part of the [Environmental Sciences Commons](#)

Recommended Citation

Matthews, Robin A.; Strecker, Angela Lee; Hilles, Michael; Pickens, Joan; Mitchell, Robert J.; Matthews, Geoffrey B.; and Western Washington University, "Lake Whatcom Monitoring Project 2018/2019 Report" (2020). *Lake Whatcom Annual Reports*. 28.

https://cedar.wwu.edu/lakewhat_annualreps/28

This Report is brought to you for free and open access by the Lake Whatcom at Western CEDAR. It has been accepted for inclusion in Lake Whatcom Annual Reports by an authorized administrator of Western CEDAR. For more information, please contact westerncedar@wwu.edu.

Authors

Robin A. Matthews, Angela Lee Strecker, Michael Hilles, Joan Pickens, Robert J. Mitchell, Geoffrey B. Matthews, and Western Washington University

Lake Whatcom Monitoring Project 2018/2019 Report

Dr. Robin Matthews, Emeritus
*Environmental Sciences Department
Huxley College of the Environment*

Dr. Angela Strecker
Michael Hilles
Joan Pickens
*Institute for Watershed Studies,
Huxley College of the Environment*

Dr. Robert Mitchell
*Geology Department,
College of Science and Engineering*

Dr. Geoffrey Matthews, Emeritus
*Computer Science Department
College of Science and Engineering*

Western Washington University
Bellingham, Washington 98225

February 6, 2020

Funding for this project was provided by the City of Bellingham, as part of their long-term commitment to environmental education and their concern for maintaining the water quality of Lake Whatcom. We thank Marilyn Desmul, Diane Rydberg, Tessa Beaver, Bobbi Bevacqua, Ian Browning, Emily Deardorff, Kayla Galacia, Michael Lawlor, Beth Loper, Garrett McHugh, Olivia Mueller, Kris Staples-Weyrauch, Charles Surdyk, Aurora Watts, and Elliese Wright for assistance with the project.

(This page blank)

Contents

1	Background	1
1.1	Objectives	2
2	Lake Whatcom Monitoring	2
2.1	Site Descriptions	2
2.2	Field Sampling and Analytical Methods	3
2.3	Results and Discussion	3
2.3.1	Dissolved oxygen	5
2.3.2	Conductivity and pH	8
2.3.3	Alkalinity and turbidity	9
2.3.4	Nitrogen and phosphorus	9
2.3.5	Chlorophyll, plankton, and Secchi depth	13
2.3.6	Coliform bacteria	14
2.3.7	Total organic carbon and disinfection by-products	15
3	Tributary Monitoring	54
3.1	Site Descriptions	54
3.2	Field Sampling and Analytical Methods	54
3.3	Results and Discussion	55
4	Storm Water Monitoring	74
4.1	Hydrograph Monitoring	74
4.2	Site Descriptions	74
4.3	Field Sampling and Analytical Methods	74

5	References and Related Reports	83
5.1	Cited References	83
5.2	Related Reports	87
A	Site Descriptions	91
A.1	Lake Whatcom Monitoring Sites	91
A.2	Tributary Monitoring Sites	91
A.3	Storm Water Monitoring Sites	93
B	Long-Term Water Quality Figures	97
B.1	Monthly YSI Profiles	98
B.2	Long-term YSI/Hydrolab Data (1988-present)	149
B.3	Long-term Water Quality Data (1988-present)	170
B.4	Lake Whatcom Tributary Data (2004-present)	231
C	Quality Control	272
C.1	Performance Evaluation Reports	272
C.2	Laboratory Duplicates, Spikes, and Check Standards	272
C.3	Field Duplicates	272
D	Lake Whatcom Online Data	323

List of Figures

2.1	October 2018 temperature and dissolved oxygen compared to historic ranges	26
2.2	November 2018 temperature and dissolved oxygen compared to historic ranges	27
2.3	December 2018 temperature and dissolved oxygen compared to historic ranges	28
2.4	February 2019 temperature and dissolved oxygen compared to historic ranges	29
2.5	April 2019 temperature and dissolved oxygen compared to historic ranges	30
2.6	May 2019 temperature and dissolved oxygen compared to historic ranges	31
2.7	June 2019 temperature and dissolved oxygen compared to historic ranges	32
2.8	July 2019 temperature and dissolved oxygen compared to historic ranges	33
2.9	August 2019 temperature and dissolved oxygen compared to historic ranges	34
2.10	September 2019 temperature and dissolved oxygen compared to historic ranges	35
2.11	October 2019 temperature and dissolved oxygen compared to historic ranges	36
2.12	November 2019 temperature and dissolved oxygen compared to historic ranges	37
2.13	December 2019 temperature and dissolved oxygen compared to historic ranges (preliminary data)	38
2.14	Relationship between dissolved oxygen and time at Site 1, 12 m .	39
2.15	Relationship between dissolved oxygen and time at Site 1, 14 m .	40

2.16	Relationship between dissolved oxygen and time at Site 1, 16 m	41
2.17	Relationship between dissolved oxygen and time at Site 1, 18 m	42
2.18	Minimum summer, near-surface DIN concentrations	43
2.19	Median spring vs. summer near-surface DIN concentrations	44
2.20	Differences between spring and summer near-surface DIN concentrations	45
2.21	Median summer, near-surface total phosphorus concentrations	46
2.22	Median summer near-surface chlorophyll concentrations	47
2.23	Log ₁₀ plots of median summer, near-surface algae counts	48
2.24	Log ₁₀ plots of median summer, near-surface Cyanobacteria counts	49
2.25	THMs in the Bellingham water distribution system	50
2.26	Quarterly THMs in the Bellingham water distribution system	51
2.27	HAAs in the Bellingham water distribution system	52
2.28	Quarterly HAAs in the Bellingham water distribution system	53
4.1	Austin Creek hydrograph for WY2019	79
4.2	Smith Creek hydrograph for WY2019	80
4.3	Aquarius rating curve for Austin Creek	81
4.4	Aquarius rating curve for Smith Creek	82
A1	Lake Whatcom lake sampling sites	95
A2	Lake Whatcom tributary and storm water sampling sites	96
B1	Water column profiles for Site 1, Oct. 4, 2018	99
B2	Water column profiles for Site 2, Oct. 4, 2018	100
B3	Water column profiles for the Intake, Oct. 4, 2018	101
B4	Water column profiles for Site 3, Oct. 2, 2018	102
B5	Water column profiles for Site 4, Oct. 2, 2018	103

B6	Water column profiles for Site 1, Nov. 8, 2018	104
B7	Water column profiles for Site 2, Nov. 8, 2018	105
B8	Water column profiles for the Intake, Nov. 8, 2018	106
B9	Water column profiles for Site 3, Nov. 6, 2018	107
B10	Water column profiles for Site 4, Nov. 6, 2018	108
B11	Water column profiles for Site 1, Dec. 6, 2018	109
B12	Water column profiles for Site 2, Dec. 6, 2018	110
B13	Water column profiles for the Intake, Dec. 6, 2018	111
B14	Water column profiles for Site 3, Dec. 4, 2018	112
B15	Water column profiles for Site 4, Dec. 4, 2018	113
B16	Water column profiles for Site 1, Feb. 15, 2019	114
B17	Water column profiles for Site 2, Feb. 15, 2019	115
B18	Water column profiles for the Intake, Feb. 15, 2019	116
B19	Water column profiles for Site 3, Feb. 15, 2019	117
B20	Water column profiles for Site 4, Feb. 15, 2019	118
B21	Water column profiles for Site 1, Apr. 16, 2019	119
B22	Water column profiles for Site 2, Apr. 16, 2019	120
B23	Water column profiles for the Intake, Apr. 16, 2019	121
B24	Water column profiles for Site 3, Apr. 11, 2019	122
B25	Water column profiles for Site 4, Apr. 9, 2019	123
B26	Water column profiles for Site 1, May 9, 2019	124
B27	Water column profiles for Site 2, May 9, 2019	125
B28	Water column profiles for the Intake, May 9, 2019	126
B29	Water column profiles for Site 3, May 7, 2019	127
B30	Water column profiles for Site 4, May 7, 2019	128

B31	Water column profiles for Site 1, Jun. 6, 2019	129
B32	Water column profiles for Site 2, Jun. 6, 2019	130
B33	Water column profiles for the Intake, Jun. 6, 2019	131
B34	Water column profiles for Site 3, Jun. 10, 2019	132
B35	Water column profiles for Site 4, Jun. 10, 2019	133
B36	Water column profiles for Site 1, Jul. 11, 2019	134
B37	Water column profiles for Site 2, Jul. 11, 2019	135
B38	Water column profiles for the Intake, Jul. 11, 2019	136
B39	Water column profiles for Site 3, Jul. 9, 2019	137
B40	Water column profiles for Site 4, Jul. 9, 2019	138
B41	Water column profiles for Site 1, Aug. 8, 2019	139
B42	Water column profiles for Site 2, Aug. 8, 2019	140
B43	Water column profiles for the Intake, Aug. 8, 2019	141
B44	Water column profiles for Site 3, Aug. 6, 2019	142
B45	Water column profiles for Site 4, Aug. 6, 2019	143
B46	Water column profiles for Site 1, Sept. 10, 2019	144
B47	Water column profiles for Site 2, Sept. 10, 2019	145
B48	Water column profiles for the Intake, Sept. 10, 2019	146
B49	Water column profiles for Site 3, Sept. 10, 2019	147
B50	Water column profiles for Site 4, Sept. 3, 2019	148
B51	Historic temperature data for Site 1	150
B52	Historic temperature data for Site 2	151
B53	Historic temperature data for the Intake	152
B54	Historic temperature data for Site 3	153
B55	Historic temperature data for Site 4	154

B56	Historic dissolved oxygen data for Site 1	155
B57	Historic dissolved oxygen data for Site 2	156
B58	Historic dissolved oxygen data for the Intake	157
B59	Historic dissolved oxygen data for Site 3	158
B60	Historic dissolved oxygen data for Site 4	159
B61	Historic pH data for Site 1	160
B62	Historic pH data for Site 2	161
B63	Historic pH data for the Intake	162
B64	Historic pH data for Site 3	163
B65	Historic pH data for Site 4	164
B66	Historic conductivity data for Site 1	165
B67	Historic conductivity data for Site 2	166
B68	Historic conductivity data for the Intake	167
B69	Historic conductivity data for Site 3	168
B70	Historic conductivity data for Site 4	169
B71	Alkalinity data for Site 1	171
B72	Alkalinity data for Site 2	172
B73	Alkalinity data for the Intake site	173
B74	Alkalinity data for Site 3	174
B75	Alkalinity data for Site 4	175
B76	Turbidity data for Site 1	176
B77	Turbidity data for Site 2	177
B78	Turbidity data for the Intake site	178
B79	Turbidity data for Site 3	179
B80	Turbidity data for Site 4	180

B81	Ammonium data for Site 1	181
B82	Ammonium data for Site 2	182
B83	Ammonium data for the Intake site	183
B84	Ammonium data for Site 3	184
B85	Ammonium data for Site 4	185
B86	Nitrate/nitrite data for Site 1	186
B87	Nitrate/nitrite data for Site 2	187
B88	Nitrate/nitrite data for the Intake site	188
B89	Nitrate/nitrite data for Site 3	189
B90	Nitrate/nitrite data for Site 4	190
B91	Total nitrogen data for Site 1	191
B92	Total nitrogen data for Site 2	192
B93	Total nitrogen data for the Intake site	193
B94	Total nitrogen data for Site 3	194
B95	Total nitrogen data for Site 4	195
B96	Soluble phosphate data for Site 1	196
B97	Soluble phosphate data for Site 2	197
B98	Soluble phosphate data for the Intake site	198
B99	Soluble phosphate data for Site 3	199
B100	Soluble phosphate data for Site 4	200
B101	Total phosphorus data for Site 1	201
B102	Total phosphorus data for Site 2	202
B103	Total phosphorus data for the Intake site	203
B104	Total phosphorus data for Site 3	204
B105	Total phosphorus data for Site 4	205

B106	Chlorophyll data for Site 1	206
B107	Chlorophyll data for Site 2	207
B108	Chlorophyll data for the Intake site	208
B109	Chlorophyll data for Site 3	209
B110	Chlorophyll data for Site 4	210
B111	Secchi depths for Site 1	211
B112	Secchi depths for Site 2	212
B113	Secchi depths for the Intake site	213
B114	Secchi depths for Site 3	214
B115	Secchi depths for Site 4	215
B116	Fecal coliform data for Site 1	216
B117	Fecal coliform data for Site 2	217
B118	Fecal coliform data for the Intake site	218
B119	Fecal coliform data for Site 3	219
B120	Fecal coliform data for Site 4	220
B121	Plankton data for Site 1	221
B122	Plankton data for Site 2	222
B123	Plankton data for the Intake Site	223
B124	Plankton data for Site 3	224
B125	Plankton data for Site 4	225
B126	Plankton data for Site 1 (omit Chrysophyta)	226
B127	Plankton data for Site 2 (omit Chrysophyta)	227
B128	Plankton data for the Intake Site (omit Chrysophyta)	228
B129	Plankton data for Site 3 (omit Chrysophyta)	229
B130	Plankton data for Site 4 (omit Chrysophyta)	230

B131	Temperature data for Anderson, Austin, Smith, and Whatcom Creeks	233
B132	Temperature data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	234
B133	Temperature data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	235
B134	Dissolved oxygen data for Anderson, Austin, Smith, and Whatcom Creeks	236
B135	Dissolved oxygen data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	237
B136	Dissolved oxygen data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	238
B137	pH data for Anderson, Austin, Smith, and Whatcom Creeks	239
B138	pH data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	240
B139	pH data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	241
B140	Conductivity data for Anderson, Austin, Smith, and Whatcom Creeks	242
B141	Conductivity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	243
B142	Conductivity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	244
B143	Alkalinity data for Anderson, Austin, Smith, and Whatcom Creeks	245
B144	Alkalinity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	246
B145	Alkalinity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	247
B146	Total suspended solids data for Anderson, Austin, Smith, and Whatcom Creeks	248

B147	Total suspended solids data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	249
B148	Total suspended solids data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	250
B149	Turbidity data for Anderson, Austin, Smith, and Whatcom Creeks	251
B150	Turbidity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	252
B151	Turbidity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	253
B152	Ammonium data for Anderson, Austin, Smith, and Whatcom Creeks	254
B153	Ammonium data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	255
B154	Ammonium data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	256
B155	Nitrate/nitrite data for Anderson, Austin, Smith, and Whatcom Creeks	257
B156	Nitrate/nitrite data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	258
B157	Nitrate/nitrite data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	259
B158	Total nitrogen data for Anderson, Austin, Smith, and Whatcom Creeks	260
B159	Total nitrogen data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	261
B160	Total nitrogen data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	262
B161	Soluble phosphate data for Anderson, Austin, Smith, and Whatcom Creeks	263

B162	Soluble phosphate data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	264
B163	Soluble phosphate data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	265
B164	Total phosphorus data for Anderson, Austin, Smith, and Whatcom Creeks	266
B165	Total phosphorus data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks	267
B166	Total phosphorus data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain	268
B167	Fecal coliform data for Anderson, Austin, Smith, and Whatcom Creeks (short scale)	269
B168	Fecal coliform data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks (short scale)	270
B169	Fecal coliform data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain (short scale)	271
C1	Alkalinity laboratory duplicates	274
C2	Alkalinity high-range check standards	275
C3	Alkalinity low-range check standards	276
C4	Chlorophyll laboratory duplicates	277
C5	Conductivity laboratory duplicates	278
C6	Dissolved oxygen laboratory duplicates	279
C7	Nitrogen (ammonium) laboratory duplicates	280
C8	Nitrogen (ammonium) spike recoveries	281
C9	Nitrogen (ammonium) high-range check standards	282
C10	Nitrogen (ammonium) low-range check standards	283
C11	Nitrogen (nitrate/nitrite) laboratory duplicates	284

C12	Nitrogen (nitrate/nitrite) spike recoveries	285
C13	Nitrogen (nitrate/nitrite) high-range check standards	286
C14	Nitrogen (nitrate/nitrite) low-range check standards	287
C15	Nitrogen (total) laboratory duplicates	288
C16	Nitrogen (total) spike recoveries	289
C17	Nitrogen (total) high-range check standards	290
C18	Nitrogen (total) low-range check standards	291
C19	Laboratory pH duplicates	292
C20	Phosphorus (soluble reactive phosphate) laboratory duplicates	293
C21	Phosphorus (soluble reactive phosphate) spike recoveries	294
C22	Phosphorus (soluble reactive phosphate) high-range check standards	295
C23	Phosphate (soluble reactive phosphate) low-range check standards	296
C24	Phosphorus (total) laboratory duplicates	297
C25	Phosphorus (total) spike recoveries	298
C26	Phosphorus (total) high-range check standards	299
C27	Phosphorus (total) low-range check standards	300
C28	Total suspended solids laboratory duplicates	301
C29	Total suspended solids check standards	302
C30	Turbidity laboratory duplicates	303
C31	Alkalinity field duplicates (lake samples)	304
C32	Alkalinity field duplicates (tributary samples)	305
C33	Chlorophyll field duplicates (lake samples)	306
C34	Conductivity field duplicates (lake samples)	307
C35	Dissolved oxygen field duplicates (lake samples)	308

C36	Dissolved oxygen field duplicates (tributary samples)	309
C37	Nitrogen (ammonium) field duplicates (lake samples)	310
C38	Nitrogen (ammonium) field duplicates (tributary samples)	311
C39	Nitrogen (nitrate/nitrite) field duplicates (lake samples)	312
C40	Nitrogen (nitrate/nitrite) field duplicates (tributary samples)	313
C41	Nitrogen (total) field duplicates (lake samples)	314
C42	Nitrogen (total) field duplicates (tributary samples)	315
C43	Field duplicates for pH (lake samples)	316
C44	Phosphorus (soluble reactive phosphate) field duplicates (tributary samples)	317
C45	Phosphorus (total) field duplicates (lake samples)	318
C46	Phosphorus (total) field duplicates (tributary samples)	319
C47	Total suspended solids field duplicates (tributary samples)	320
C48	Turbidity field duplicates (lake samples)	321
C49	Turbidity field duplicates (tributary samples)	322

List of Tables

2.1	Analytical methods and parameter abbreviations	17
2.2	Lake Whatcom annual lake monitoring summary. All field and laboratory methods are summarized in Table 2.1.	18
2.3	Summary of Site 1 water quality data, Oct. 2018 – Sept. 2019. . .	19
2.4	Summary of Intake water quality data, Oct. 2018– Sept. 2019. . .	20
2.5	Summary of Site 2 water quality data, Oct. 2018 – Sept. 2019. . .	21
2.6	Summary of Site 3 water quality data, Oct. 2018 – Sept. 2019. . .	22
2.7	Summary of Site 4 water quality data, Oct. 2018 – Sept. 2019. . .	23
2.8	October hypolimnetic hydrogen sulfide concentrations	24
2.9	Lake Whatcom 2018/2019 total organic carbon data	25
3.1	Lake Whatcom monthly tributary monitoring summary. All field and laboratory methods are summarized in Table 2.1.	59
3.2	Comparison of 2018–2019 water quality in Lake Whatcom tributaries	60
3.3	Anderson Creek water quality data, October 2018-September 2019	61
3.4	Austin Creek water quality data, October 2018-September 2019 .	62
3.5	Blue Canyon Creek water quality data, October 2018-September 2019	63
3.6	Brannian Creek water quality data, October 2018-September 2019	64
3.7	Carpenter Creek water quality data, October 2018-September 2019	65
3.8	Euclid Creek water quality data, October 2018-September 2019 .	66
3.9	Millwheel Creek water quality data, October 2018-September 2019	67
3.10	Olsen Creek water quality data, October 2018-September 2019 . .	68
3.11	Park Place outlet water quality data, October 2018-September 2019	69

3.12	Silver Beach Creek water quality data, October 2018-September 2019	70
3.13	Smith Creek water quality data, October 2018-September 2019 . .	71
3.14	Whatcom Creek water quality data, October 2018-September 2019	72
3.15	Lake Whatcom 2019 tributary total organic carbon data	73
4.1	Austin Creek rating curves for WY2019	76
4.2	Smith Creek rating curves for WY2019	77
4.3	Summary of storm events for Austin, Euclid, and Silver Beach Creeks	78
A1	Approximate GPS coordinates for Lake Whatcom sampling sites.	94
B1	List of outliers omitted from Figures B131–B169	232
C1	Single-blind quality control results	273

Executive Summary

Background for the Lake Whatcom Annual Reports

- This report describes the results from the 2018/2019 Lake Whatcom monitoring program conducted by the Institute for Watershed Studies at Western Washington University (www.wwu.edu/iws).
- The major objectives in 2018/2019 were to continue long-term baseline water quality monitoring in Lake Whatcom and its major tributaries; collect storm runoff water quality data from representative streams in the watershed; and continue collection of hydrologic data from Austin and Smith Creeks.
- Each section in this report contains a brief discussion of the water quality parameters that are measured as part of the monitoring effort. For additional help with understanding the relationship between water quality data and lake, stream, or watershed ecology, we recommend the online resource “Water on the Web” (WOW, 2004; www.waterontheweb.org).
- The online pdf copy of this report contains **red hyperlinks** that will open online citations, and **blue hyperlinks** that will jump to referenced tables and figures or to the section that contains additional information about a specific topic. These hyperlinks are active if the report is opened using Adobe Reader, which can be downloaded free from www.adobe.com/products/reader.html.
- This report is part of an on-going series of annual reports and special project reports that provide a complete documentation of the monitoring program over time. A summary of the Institute for Watershed Studies Lake Whatcom reports, including special project reports, is included in Section 5.2, beginning on page 87, and many of the reports are available online through Western CEDAR, the WWU repository for open access scholarship, under the Institute for Watershed Studies Lake Whatcom collection (http://cedar.wwu.edu/iws_lakewhatcom).

Summary of 2018/2019 Monitoring Project

- During the summer the lake's water column was [thermally stratified](#) into a warm surface layer (the epilimnion) and a cool bottom layer (the hypolimnion). Most of the 2018/2019 temperature profiles fell within historic ranges, with stable stratification present at Sites 1–4 by early June. (Section [2.3](#), page [4](#)).¹
- The [hypolimnetic oxygen](#) concentrations have declined over time at Site 1 (Section [2.3.1](#), page [5](#)), causing the lake to be listed by the Department of Ecology on the 1998 303d list of impaired waterbodies in the state of Washington. The hypolimnetic oxygen loss was apparent at Site 1 after the lake became fully stratified in June, and by August the oxygen concentrations were <2 mg/L from 12 meters to the bottom.
- [Nitrate depletion](#) was evident at all sites in the photosynthetic zone during the summer due to algal uptake of this essential nutrient (Section [2.3.4](#), page [9](#)). Unlike the other [indicators of phytoplankton productivity](#), the dissolved inorganic nitrogen (DIN = nitrate + nitrite + ammonium) trend has not stabilized in recent years. A month-by-month analysis of near-surface DIN showed that water column concentrations have declined in general, not just in the summer. Nitrate depletion also occurred in the hypolimnion at Sites 1 and 2 due to nitrate reduction by bacteria. Anaerobic conditions in the hypolimnion at Sites 1 and 2 resulted in elevated concentrations of ammonium by the end of the summer.
- The summer near-surface [total phosphorus](#) concentrations continued to follow erratic patterns, with no significant correlations with year (Section [2.3.4](#), page [11](#)), reflecting the complicated nature of phosphorus movement in the water column.
- The summer near-surface [chlorophyll concentrations](#) have increased significantly over time at all sites (Section [2.3.5](#), page [13](#)). Despite being quite variable, the concentrations appear to have stabilized since 2004, ranging from 3.8–6.7 $\mu\text{g/L}$ at Site 1 and 2.6–4.6 $\mu\text{g/L}$ at Sites 2–4.

¹These links direct the reader to sections with additional information on the summary topic.

- All of the mid-basin **coliform counts** were less than 10 cfu/100 mL (Section 2.3.6, page 14). The coliform counts at the Bloedel-Donovan recreational area (collected offshore from the swimming area) were slightly higher than mid-basin counts, but passed the freshwater *Primary Contact Recreational* bacteria standard for Washington.
- The concentrations of **trihalomethanes and haloacetic acids** (THMs and HAAs) in Bellingham’s treated drinking water have been increasing over time, but the concentrations of both types of disinfection by-products remained below the maximum contaminant levels of 0.080 mg/L and 0.060 mg/L, respectively (Section 2.3.7, page 15).
- **Monthly tributary samples** were collected at 12 locations in the Lake Whatcom watershed (Section 3, page 54). Due to a dry spring and summer, five of the sites could not be sampled on one or more of the sampling trips.
- Most of the tributaries had low concentrations of total suspended solids, low alkalinities and conductivities, and low levels of nutrients (phosphorus and nitrogen). The residential streams had higher concentrations of total suspended solids, higher alkalinities and conductivities, higher coliform counts, and higher nutrient concentrations.
- **Hydrograph data** were collected at Austin and Smith Creeks using rating curves developed with Aquarius software to calculate discharge (Section 4.1, page 74).
- **Storm runoff samples** were collected in Austin Creek (four storm events), Euclid Creek (seven storm events), and Silver Beach Creek (six storm events) using time-paced automated samplers (Section 4, page 74). The water quality data are sent to the City of Bellingham for use in watershed modeling.

(This page blank)

1 Background

This report is part of an on-going series of annual reports and special project reports that document the Lake Whatcom monitoring program over time. Many of the reports are available online through Western CEDAR, the WWU repository for open access scholarship, under the Institute for Watershed Studies Lake Whatcom collection (http://cedar.wvu.edu/iws_lakewhatcom). Reports that are not available on CEDAR may be available in the Institute for Watershed Studies (IWS) library or through the City of Bellingham Public Works Department. A summary of the Lake Whatcom annual and special project reports is included in Section 5.2, beginning on page 87.

Each section in this report contains a brief discussion of the water quality parameters that are measured as part of the monitoring effort. For additional help with understanding the relationship between water quality data and lake, stream, or watershed ecology, we recommend the online resource “Water on the Web” (www.waterontheweb.org; WOW, 2004).

Lake Whatcom is the primary drinking water source for the City of Bellingham and parts of Whatcom County, including Sudden Valley. It also serves as a primary or supplemental water source to various consecutive water systems to the City of Bellingham.

The lake and its watershed provide recreational opportunities, as well as important habitats for fish and wildlife. The lake is used as a storage reservoir to buffer peak storm water flows in Whatcom Creek. Because of its aesthetic appeal, the watershed is highly valued for residential development. Historically, most of the nonresidential portion of the watershed was zoned for forestry and was managed by state or private timber companies.

In January 22, 2014, approximately 8,800 acres of forest lands formerly managed by the Department of Natural Resources was reconveyed to Whatcom County to be managed as low impact park lands. The Lake Whatcom reconveyance planning process is summarized online at www.whatcomcounty.us/625/Lake-Whatcom-Reconveyance.

1.1 Objectives

The City of Bellingham and Western Washington University have collaborated on water quality studies in Lake Whatcom since the early 1960s. Beginning in 1988, a monitoring program was initiated by the City and WWU that was designed to provide long-term lake data for temperature, pH, dissolved oxygen, conductivity, turbidity, nutrients (nitrogen and phosphorus), and other representative water quality measurements. The major goal of the long-term monitoring effort is to provide a record of Lake Whatcom's water quality over time.

The major objectives of the 2018/2019 Lake Whatcom monitoring program were to continue long-term baseline water quality monitoring in Lake Whatcom and its major tributaries; collect storm runoff water quality data from representative streams in the watershed; and continue collection of hydrologic data from Austin and Smith Creeks.

Detailed site descriptions can be found in Appendix A. The historic lake data are plotted in Appendix B. The current quality control results are in Appendix C. The monitoring data are available online at www.wwu.edu/iws as described in Appendix D (page 323). Table 2.1 (page 17) lists abbreviations and units used to describe water quality analyses; Tables 2.2 & 3.1 (pages 18 & 59) list the locations, depths, and frequency for lake and tributary sampling

2 Lake Whatcom Monitoring

2.1 Site Descriptions

Water quality samples were collected at five long-term monitoring sites in Lake Whatcom (Figure A1, page 95 in Appendix A.1). Sites 1–2 are located at the deepest points in their respective basins. The Intake site is located adjacent to the underwater intake point where the City of Bellingham withdraws lake water from basin 2. Site 3 is located at the deepest point in the northern sub-basin of basin 3 and Site 4 is located at the deepest point in the southern sub-basin of basin 3. Water samples were also collected at the City of Bellingham Lake Whatcom Gatehouse, which is located onshore and west of the Intake site.

2.2 Field Sampling and Analytical Methods

The lake was sampled on October 2 & 4, November 6 & 8, and December 4 & 6, 2018; and February 15, April 9, 11, & 16, May 7 & 9, June 6 & 10, July 9 & 11, August 6 & 8, and September 3 & 10, 2019. Each sampling event is a multi-day task; all samples were collected during daylight hours, typically between 10:00 am and 3:00 pm. The analytical and sampling procedures are summarized in Tables 2.1 & 2.2 (pages 17 & 18).

A YSI EXO1 multiparameter field meter was used to measure temperature, pH, dissolved oxygen, and conductivity in the field. Raw water and bacteriological samples were collected using a VanDorn sampler; plankton samples were collected using a 30-L Schindler trap equipped with a 20 μm mesh plankton net. The water and bacteriological samples were stored on ice and in the dark until they reached the laboratory. Plankton samples were placed in a cooler and returned to the laboratory unpreserved. The plankton sample volumes were measured in the laboratory and the samples were preserved with Lugol's solution. Total organic carbon analyses were done by AmTest² and by IWS. The bacteria samples were analyzed by the City of Bellingham.

2.3 Results and Discussion

The lake monitoring data include monthly field measurements (conductivity, dissolved oxygen, pH, Secchi depth, and water temperature); laboratory analyses for ambient water quality parameters (ammonium,³ nitrate/nitrite,⁴ total nitrogen, soluble phosphate, total phosphorus, alkalinity, turbidity, chlorophyll); plankton and bacteria counts; and total organic carbon measurements.

²AmTest, 13600 Northeast 126th Place, Suite C, Kirkland, WA, 98034-8720.

³Ammonium (NH_4^+) is ionized ammonia (NH_3). Nearly all ammonia is ionized in surface water. Earlier IWS reports used the term ammonia and ammonium interchangeably to describe ammonium concentrations because it is generally understood that ammonia is usually ionized. To improve clarity, IWS has switched to the term "ammonium" to indicate that we are reporting the concentration of ionized ammonia. This does not represent any change in analytical methods.

⁴Nitrate and nitrite were analyzed together because nitrite concentrations are very low in surface water and require low level analytical techniques to measure accurately. For simplicity, nitrate/nitrite will be referred to as "nitrate" in this document.

The 2018/2019 temperature, dissolved oxygen, pH, and conductivity profiles are shown in Figures B1–B50 (Appendix B, pages 99–148). Tables 2.3–2.7 (pages 19–23) summarize the current field measurements, ambient water quality, and coliform data, and all of the current data are plotted in comparison with historic data in Figures B51–B130 (Appendix B, pages 150–230). These figures are scaled to plot the full range of Lake Whatcom water quality data including minimum, maximum, and outlier values, and do not provide the best illustration of trends that occur in the lake. Separate tables and figures are provided to show trends and illustrate specific patterns in the data. The raw data are available online at www.wvu.edu/iws as described in Appendix D (page 323).

The 2018/2019 monthly temperature profiles for Sites 1–4 were plotted as overlay points on shaded polygons that summarize the 1988–2019 historic temperature ranges (Figures 2.1–2.13, pages 26–38).⁵ The monthly YSI profiles for temperature, dissolved oxygen, pH, and conductivity at Sites 1–4 and the Intake were included in Appendix B (Figures B1–B50, pages 99–148).

The summer temperature profiles (e.g., Figure 2.7, page 32) show how the lake stratifies into a warm surface layer (*epilimnion*), and cool bottom layer (*hypolimnion*). The transition zone between the epilimnion and hypolimnion (*metalimnion*) is a region of rapidly changing water temperature. When stratified, the temperature profiles show distinct differences between the surface and bottom of the water column. Stratification develops gradually, and once stable, persists until fall or winter, depending on location in the lake. Seasonal weather differences alter the timing of lake stratification; if the spring is cool, cloudy, and windy, the lake may stratify later than when it has been hot and sunny.

In Lake Whatcom, all sites except the Intake⁶ are usually stratified by late spring or early summer. Stratification may begin as early as April, but is often not stable until May or June. The stability of stratification is determined in part by the temperature differences in the water column, but also by water circulation and local weather patterns. Once the water column temperature differs by at least 5°C ($\Delta T \geq 5^\circ\text{C}$), it is unlikely that the lake will destratify.⁷

⁵October–December 2019 are not part of the 2018/2019 sampling period, but the temperature/oxygen profiles were included to provide information on the timing of destratification.

⁶The Intake is too shallow to develop stable stratification (see Appendix B, Figures B1–B46).

⁷The ΔT is the difference between the epilimnion and hypolimnion temperatures.

As the weather becomes colder and days shorten, the lake cools and the surface and bottom water temperatures become more similar. Eventually the water column will start to mix from the surface to the bottom and the lake will destratify. Basins 1 and 2 (Sites 1–2) usually destratify by the end of October or early November, but basin 3 (Sites 3–4) is usually still stratified in November (Figure 2.2, page 27). Complete destratification of basin 3 occurs in December or early January, so by February the temperatures are uniform throughout the water column at all sites (Figure 2.4, page 29).

Although destratification is relatively abrupt, the process of mixing the entire water column is not instantaneous. When the lake begins to destratify, water temperatures may be uniform from the surface to the bottom, but the rate of water circulation may not be sufficient to replenish hypolimnetic oxygen concentrations. This phenomenon, where temperature is uniform, but dissolved compounds (e.g., dissolved oxygen) remain partially stratified, is common in the early stages of destratification, when the basin is starting to mix (see November 2013 temperature and oxygen profiles from Site 2; Figure B.7 in Matthews, et al., 2015).

The lake was still stratified at all sites in October 2018 (Figure 2.1, page 26). Site 1 was completely destratified by November but Site 2 still showed a slight temperature difference near the bottom (Figure 2.2, page 27). Sites 3–4 were close to destratification in December 2018 ($\Delta T \leq 4^\circ \text{C}$); the entire lake was destratified in February 2019 (Figures 2.3–2.4, pages 28–29).

The water column was beginning to stratify in April 2019 ($\Delta T = 2.8\text{--}4.0^\circ \text{C}$) but did not develop stable stratification until May (Figures 2.5–2.6, pages 30–31). All sites remained stratified through September, with temperatures falling within typical historic ranges. (Figures 2.7–2.10, pages 32–35).

2.3.1 Dissolved oxygen

The 2018/2019 monthly oxygen profiles for Sites 1–4 were plotted as overlay points on shaded polygons that summarize the 1988–2019 historic temperature ranges (Figures 2.1–2.13, pages 26–38).⁸ The monthly YSI profiles for temperature, dissolved oxygen, pH, and conductivity at Sites 1–4 and the Intake were included in Appendix B (Figures B1–B50, pages 99–148).

⁸October–December 2019 are not part of the 2018/2019 sampling period, but the temperature/oxygen profiles were included to provide information on the timing of destratification.

As in past years, Sites 1–2 developed severe hypolimnetic oxygen deficits during the summer (Figures 2.8–2.10, pages 33–35). Hypolimnetic oxygen depletion only becomes apparent after stratification, when the lower waters of the basin are isolated from the lake’s surface and biological respiration consumes the oxygen dissolved in the water. Biological respiration usually increases when there is an abundant supply of organic matter (e.g., decomposing algae). In basin 3, which has a very large, well-oxygenated hypolimnion, respiration has relatively little influence on hypolimnetic oxygen concentrations. In contrast, there is rapid depletion of the hypolimnetic oxygen concentrations at Sites 1–2. These two sites are in shallow basins that have small hypolimnions compared to their photic zones⁹ so decomposition of algae and other organic matter causes a significant drop in hypolimnetic oxygen over the summer. This oxygen depletion may be apparent as early as May if the lake stratifies in April, but the lake didn’t stratify until May in 2019 so the oxygen depletion at Sites 1–2 was not obvious until June (Figure 2.7, page 32).

Low oxygen conditions are associated with a number of unappealing water quality problems in lakes, including loss of aquatic habitat; release of phosphorus from the sediments; increased rates of algal production due to release of phosphorus; unpleasant odors during lake destratification; fish kills, particularly during lake destratification; release of metals and organics from the sediments; increased mercury methylation; increased drinking water treatment costs; increased taste and odor problems in drinking water; and increased risks associated with disinfection by-products created during the drinking water treatment process.

The levels of hypolimnetic oxygen have declined over time at Site 1, causing the lake to be listed by the Department of Ecology as an “impaired” waterbody (Pelletier, 1998).¹⁰ The increasing rate of oxygen loss is most apparent during July and August, after the lake develops stable stratification but before oxygen levels drops near zero. To illustrate this trend we fitted the July and August data using an exponential function (see discussion by Matthews, et al., 2004). As indicated in Figures 2.14–2.17 (pages 39–42), there were significant negative correlations¹¹

⁹The photic zone is the region with enough light to support algal photosynthesis, which extends to about 10 m below the surface in Lake Whatcom. Assuming a photic zone of 0–10 m, the photic zones for basins 1, 2, and 3 would be 75%, 70%, and 17%, respectively (Mitchell, et al., 2010).

¹⁰www.ecy.wa.gov/programs/wq/303d.

¹¹ Correlation analyses examine the relationships between two variables. The test statistic ranges from –1 to +1; the closer to ± 1 , the stronger the correlation. The significance is measured using the p-value; significant correlations have p-values <0.05.

between dissolved oxygen and time for all hypolimnetic samples collected during July and August. Although Site 1 didn't develop stable stratification until May, the July hypolimnetic oxygen concentrations were already <4 mg/L and by August the oxygen concentrations were <1 mg/L (Figures 2.14–2.17).

A region of supersaturated oxygen was evident in the metalimnion at Site 1 in June and July (Figures 2.7–2.8, pages 32–33; Figures B31 & B36, pages 129 & 134). This was caused by the accumulation of phytoplankton along the density gradient between the epilimnion and hypolimnion where light and nutrients are sufficient to support very high levels of photosynthesis. Chlorophyll concentrations within the metalimnetic oxygen peak may be 4–5 times higher than those measured near the surface of the lake (Matthews and DeLuna, 2008). Metalimnetic oxygen peaks are common at Site 1 during the summer, and may occur at Sites 2–4, but will usually be at different depths because the metalimnions are at different depths. When present, the metalimnions form at approximately 5–10 m at Site 1, 10–15 m at Site 2, and 15–20 m at Sites 3–4.

Hypolimnetic oxygen loss is much less obvious in basin three, in part due to the much larger hypolimnetic volume. Sites 3 and 4 often develop small oxygen sags near the thermocline during late summer. These are caused by respiration of heterotrophic bacteria that accumulate along the density gradient between the epilimnion and hypolimnion (e.g., Figure 2.1, page 26; Figure B4, page 102; Matthews and DeLuna, 2008). From October through December, which is usually the last month of stratification in basin three, the hypolimnetic oxygen concentrations at Sites 3–4 are often lower than in the epilimnion (e.g., Figures 2.2 & B9, pages 27 & 107). But the hypolimnion in basin three rarely drops below 5–6 mg/L of dissolved oxygen, with the exception of the deepest samples from Site 3. Site 3 samples from 80 meters are especially problematic because that depth is very close to the lake bottom. When there is evidence of contamination from lake bottom sediments, which is indicated by elevated conductivities or unusually high pH values, the 80 m samples are omitted because they do not reflect water column conditions (e.g., Figure 2.9, page 34; Figure B44, page 142).

Hypolimnetic hydrogen sulfide: Bacteria require an energy source (e.g., organic carbon) and an electron acceptor (e.g., oxygen) for basic growth and metabolism. Under anaerobic conditions, when oxygen is not available, there is a predictable sequence whereby different types of anaerobic bacteria use alternate

electron acceptors.¹² First, bacteria will use nitrate as an alternate to oxygen, converting nitrate to nitrite or nitrogen gas. Next, bacteria use manganese and ferrous ions. When these compounds are exhausted, bacteria use sulfate, converting it to hydrogen sulfide, a colorless gas with a strong, rotten-egg smell. If the electron acceptors listed above are unavailable, bacteria can use carbon dioxide, converting it to methane.

Hydrogen sulfide is commonly present in anaerobic lake sediments, but if the overlying water contains oxygen the sulfide will be converted into sulfates or other compounds. If the overlying water is anaerobic, hydrogen sulfide can build up to detectable levels during stratification. Hydrogen sulfide is an indicator of the degree of anoxia in the hypolimnion because it will not persist in oxygenated waters and is formed after the nitrate, manganese, and ferrous ions are exhausted.

The hypolimnion at Sites 1–2 usually contain detectable concentrations of hydrogen sulfide by October (Table 2.8, page 24). Hydrogen sulfide concentrations are measured in October because that is the latest month that is consistently stratified at Sites 1–2, so the hydrogen sulfide concentrations should be near their highest levels. Stable stratification didn't develop until May 2019, so the hydrogen sulfide concentrations were relatively low.

2.3.2 Conductivity and pH

The pH and conductivity data followed trends that were fairly typical for Lake Whatcom (Figures B1–B50 and B61–B70, pages 99–148 and 160–169). Epilimnetic pH values increased during the summer due to photosynthetic activity and hypolimnetic pH values decreased due to decomposition and the release of dissolved compounds from the sediments (Figures B31–B45, pages 129–B45).

The conductivity concentrations were elevated in hypolimnetic samples at Sites 1–2, and periodically at Site 3, coinciding with periods of low oxygen near the bottom (e.g., Figures B46 & B47, pages 144 & 145). The historic data show what appears to be a decreasing trend in the conductivity values from 1988–2002, but this was caused by using increasingly sensitive equipment during the past three decades and does not indicate any actual change in the conductivity in the lake (Matthews, et al., 2004). Occasional spikes in conductivity at Site 3 are associated with low oxygen in samples collected very close to the bottom sediments.

¹²For a more complete discussion of anaerobic decomposition in lakes, see Wetzel, 2001.

2.3.3 Alkalinity and turbidity

Lake Whatcom is a soft water lake so most alkalinity values were low (≤ 25 mg/L; Figures B71–B75, pages 171–175). During the summer the alkalinity values at the bottom of Sites 1–2 increased due to decomposition and the release of dissolved compounds from the sediments into the lower portion of the water column.

Turbidity values in the lake were usually low (1–3 NTU) except during late summer in samples from near the bottom of the lake. The high turbidity levels during this time are an indication of increasing turbulence in the lower hypolimnion as the lake begins to destratify. The highest turbidity peaks were measured at Sites 1–2, followed by Site 3 (Figures B76–B80, pages 176–180).

Suspended sediments from storm events can also cause elevated turbidity levels in the lake. Major storm events usually occur during winter or early spring when the lake is destratified, so the turbidity levels will be high throughout the water column. Storm-related turbidity peaks are easier to see in samples from the Intake and Site 4 where there are fewer distracting late summer hypolimnetic turbidity peaks (e.g., Feb. 2009 turbidity peaks, Figures B78 and B80; pages 178 and 180).

2.3.4 Nitrogen and phosphorus

The nitrogen and phosphorus data are illustrated in Figures B81–B105 (pages 181–205). Nitrogen and phosphorus are important nutrients that influence the amount and type of microbiota (e.g., algae) that grow in the lake. We measured inorganic forms of nitrogen and phosphorus (nitrite, nitrate, ammonium, and soluble phosphate) as well as total nitrogen and total phosphorus, which includes inorganic and organic compounds.¹³

Nitrogen: Most algae use dissolved inorganic nitrogen (DIN)¹⁴ for growth. Nitrate depletion was evident at all sites in the photosynthetic zone during the sum-

¹³Organic nitrogen and phosphorus comes from living or decomposing plants and animals, and may include bacteria, algae, leaf fragments, and other organic particles.

¹⁴Dissolved inorganic nitrogen includes ammonium, nitrate, and nitrite. Usually, epilimnetic concentrations of ammonium and nitrite are low, so DIN is nearly equivalent to nitrate. When DIN is not available, some algae can use organic nitrogen and some Cyanobacteria, and a few uncommon species of diatoms, can convert dissolved nitrogen gas to ammonia (not ammonium) via nitrogen fixation.

mer (Figures B86–B90, pages 186–190), particularly at Site 1, where the epilimnetic nitrate concentrations usually drop below $20 \mu\text{g-N/L}$ by the end of the summer. Because nitrogen is required for algal growth, depletion of epilimnetic DIN concentrations is an indirect way to measure phytoplankton productivity. And, because algal densities have been increasing throughout the lake, it was not surprising to find that the DIN concentrations were declining over time (Figure 2.18, page 43). But, unlike the other indicators of phytoplankton productivity (see **Indications of eutrophication**, beginning on page 13), the DIN trend has not stabilized in recent years. A month-by-month analysis of near-surface DIN showed that water column concentrations have declined in general, not just in the summer (Figure 2.19, page 44). When the summer DIN concentrations were adjusted by subtracting the median spring DIN values ($\Delta\text{DIN} = \text{DIN}_{\text{spring}} - \text{DIN}_{\text{summer}}$), the trend with year was only marginally significant or not statistically significant, depending on site (Figure 2.20, page 45). The reason for the lake-wide drop in DIN is not known, but similar trends have been reported for lakes in the midwestern and northeastern region of the USA (Oliver, et al., 2017), lakes in the Sierra Nevadas (Sickman, et al., 2003), lakes in the Adirondacks (Waller, et al., 2012), as well as lakes and rivers in northern Italy (Rogora, et al., 2012). Most of these studies attribute the declining DIN concentrations to decreasing amounts of nitrogen entering lakes from atmospheric deposition, but without a detailed nitrogen budget analysis for Lake Whatcom, it would be premature to attribute the declining DIN to a specific cause. The implication, however, is that Lake Whatcom water quality conditions may become increasingly favorable for the growth of nitrogen-fixing Cyanobacteria, many of which are capable of releasing toxins. Recent summer algal counts from Lake Whatcom revealed that the lake contained many species of Cyanobacteria (Matthews, et al., 2012), but the nitrogen-fixing species were not abundant. It will be important to continue tracking the densities of Cyanobacteria in the lake and to watch for increases in the densities of nitrogen-fixing species.

Hypolimnetic nitrate concentrations dropped below $20 \mu\text{g-N/L}$ at Sites 1–2 (Figures B86–B87, pages 186–187). In anaerobic environments, bacteria reduce nitrate (NO_3^-) to nitrite (NO_2^-) and nitrogen gas (N_2). The historic data indicate that nitrate reduction has been common in the hypolimnion at Site 1, but was not common at Site 2 until the summer of 1999 (Figure B87, page 187). Since then, the only year that Site 2 hypolimnetic nitrate concentrations did not drop below $20 \mu\text{g-N/L}$ was 2007. Matthews, et al. (2008) hypothesized that the 2007 results were caused by a combination of late spring stratification and early fall destratification, which shortened the period of anoxia in the hypolimnion.

Ammonium, along with hydrogen sulfide, is often an indicator of hypolimnetic anoxia.¹⁵ Ammonium is readily taken up by plants as a growth nutrient. In oxygenated environments, ammonium is rarely present in high concentrations because it is rapidly converted to nitrate through biological and chemical processes. In low oxygen environments, like the hypolimnion at Sites 1–2, ammonium concentrations increase during late summer, reaching maximum concentrations just prior to destratification (Figures B81 & B82, pages 181 & 182). Elevated hypolimnetic ammonium concentrations have been common at both sites throughout the monitoring period, but beginning in 1999 the concentrations increased noticeably at Site 2 (Figure B82, page 182). The October 2018 samples from Sites 1–2 contained very high ammonium concentrations near the bottom of the water column, reaching 508 $\mu\text{g-N/L}$ at Site 1 (20 m) and 547 $\mu\text{g-N/L}$ at Site 2 (20 m). In 2019 the October ammonium concentrations were slightly lower (352 and 269 $\mu\text{g-N/L}$ at Sites 1 & 2, respectively), but were still elevated compared to the rest of the water column. Both sites are usually destratified by November, which causes the ammonium concentrations to drop through winter and spring (see annual patterns in Figures B81 & B82, pages 181 & 182). In November 2018, however, Site 2 was still slightly stratified (Figure B7, page 105), and the ammonium concentration at 20 m was still very high (691 $\mu\text{g-N/L}$). Site 2 was completely destratified by December 2018, and the hypolimnetic ammonium concentrations were below the analytical detection level (Table 2.1, page 17).

Sites 3–4 often have slightly elevated ammonium concentrations in the metalimnion at 20 m, or near the bottom at 80–90 m (Figures B84–B85, pages 184–185). This is caused by bacterial decomposition of organic matter, but the concentrations never approach the levels found in the hypolimnion at Sites 1–2.

Phosphorus: Although the Lake Whatcom microbiota require nitrogen, phosphorus is usually what limits microbial growth (Bittner, 1993; Liang, 1994; Matthews, et al., 2002a; McDonald, 1994). The total phosphorus concentration in the water column is a complex mixture of soluble and insoluble phosphorus compounds, only some of which can be used by algae to sustain growth. Soluble forms of phosphorus (e.g., orthophosphate) are easily taken up by algae and other microbiota, and, as a result, are rarely found in high concentrations in the

¹⁵Ammonium is produced during decomposition of organic matter; hydrogen sulfide is produced by bacteria that use sulfate (SO_4^{2-}) instead of oxygen, creating sulfide (S^{2-}) that reacts with hydrogen ions to form hydrogen sulfide (H_2S). See hydrogen sulfide discussion on page 7.

water column. Insoluble phosphorus can be present in the water column bound to the surface of tiny particles or as suspended organic matter (e.g., live or dead algae). Some microbiota produce enzymes that release phosphorus from the surface of suspended soil particles. Liang (1994) and Groce (2011) demonstrated that $\geq 50\%$ of the total phosphorus associated with soils in the Lake Whatcom watershed was potentially “bioavailable” through enzyme action. Algal growth tests revealed that 37–92% (median=78%) of the total phosphorus in storm runoff from Anderson, Austin, and Smith Creeks was bioavailable (Deacon, 2015).

When hypolimnetic oxygen concentrations are low, sediment-bound phosphorus becomes soluble and leaches into the overlying water. Prior to destratification, hypolimnetic phosphorus may be taken up by microbiota in the hypolimnion or metalimnion (see Section 2.3.1 and Matthews and DeLuna, 2008). When the lake mixes in the fall, the hypolimnetic phosphorus will be distributed throughout the water column. As oxygen concentrations increase during mixing, any soluble phosphorus that has not been taken up by biota will usually be converted back into insoluble phosphorus. Because phosphorus moves back and forth between soluble and insoluble forms and between organic and inorganic compounds, it can be difficult to interpret total phosphorus trends. For example, when algal densities increase, their growth usually results in the reduction of soluble and bioavailable fractions of phosphorus in the epilimnion. This uptake moves the phosphorus into the “live-algae” fraction of organic phosphorus, which should show up in total phosphorus measurements. But algae are not distributed homogeneously in the water column (Matthews and Deluna, 2008), making it difficult to estimate the amount of phosphorus that is incorporated into algal biomass.

In Lake Whatcom, total phosphorus and soluble phosphate concentrations were usually low except in the hypolimnion at Sites 1–2 just prior to destratification (Figures B96–B100, pages 196–200 and B101–B105, pages 201–205). Epilimnetic total phosphorus concentrations are usually lower than late-summer hypolimnetic peaks. Prior to 2000, the median epilimnetic phosphorus concentrations were $< 5 \mu\text{g-P/L}$ at Sites 2–4 and approximately $5\text{--}8 \mu\text{g-P/L}$ at Site 1 (Figure 2.21, page 46). Since 2000, the median epilimnetic phosphorus concentrations have often been in the detectable range ($\geq 5 \mu\text{g-P/L}$), but the pattern is quite erratic, reflecting the complicated nature of phosphorus movement in the water column (Figure 2.21, page 46).

2.3.5 Chlorophyll, plankton, and Secchi depth

Site 1 continued to have the highest chlorophyll concentrations of all the sites (Figures B106–B110, pages 206–210). Peak chlorophyll concentrations were usually collected at 0–15 m, while samples from 20 m had relatively low chlorophyll concentrations because light levels are not optimal for algal growth at this depth.

The plankton counts (Figures B121–B130, pages 221–230) were usually dominated by golden algae (Chrysophyta). Substantial numbers of green algae (Chlorophyta) and bluegreen bacteria (Cyanobacteria) were also measured at all sites during summer and late fall. Previous analyses of algal biomass in Lake Whatcom indicated that although Chrysophyta dominate the numerical plankton counts, Chlorophyta and Cyanobacteria may dominate the plankton biomass, particularly in late summer and early fall (Ashurst, 2003; Matthews, et al., 2002b).

Secchi depths (Figures B111–B115, pages 211–215) showed no clear seasonal pattern because transparency in Lake Whatcom is affected by particulates from storm events as well as algal blooms.

Indications of eutrophication: Eutrophication is the term used to describe a lake that is becoming more biologically productive. It can apply to an unproductive lake that is becoming slightly more eutrophic, or a productive lake that is becoming extremely eutrophic (see Wetzel, 2001, for more about eutrophication and Matthews, et al., 2005, for a description of the chemical and biological indicators of eutrophication in Lake Whatcom).

Chlorophyll is a direct measure of algal biomass and generally provides a better indication of changes in the lake's biological productivity than phosphorus. Similarly, although algal counts are useful for looking at trends within the same type of algae (e.g., are the numbers of Cyanobacteria increasing?), cell counts are not as good as chlorophyll for estimating algal biomass. The actual relationship between chlorophyll and algae cell counts is complex. The amount of chlorophyll in a cell is influenced by the physiological age and condition of the cell, light intensity, nutrient availability, and many other factors. In addition, while most types of algae are counted by individual cells, a few types must be counted by colonies because the cells are too difficult to see.

The median near-surface summer chlorophyll concentrations have increased significantly at all sites since 1994 (Figure 2.22, page 47). Site 1 has shown the most year-to-year variability, which is reflected by a slightly lower correlation statistic compared to Sites 2–4 (Site 1 Kendall's $\tau = 0.524$; Sites 2–4 Kendalls $\tau = 0.542, 0.631, 0.577$, respectively).¹⁶ Although the annual chlorophyll concentrations are quite variable, they seem to have stabilized since 2004, ranging from 3.8–6.7 $\mu\text{g/L}$ at Site 1 and 2.6–4.6 $\mu\text{g/L}$ at Sites 2–4 (Appendix B, page 97).

Except for the dinoflagellates,¹⁷ the algae counts have increased significantly since 1994 (Figure 2.23, page 48). Cyanobacteria, which are often used as bioindicators of eutrophication, have increased at all sites (Figure 2.24, page 49). The Cyanobacteria counts are dominated by *Aphanothece*, *Aphanocapsa*, *Cyanodictyon*, and *Snowella*. These genera not typically associated with toxic blooms (Granéli and Turner, 2006; Matthews, et al., 2012). As with chlorophyll, the algae and Cyanobacteria counts appear to have stabilized since 2004.

2.3.6 Coliform bacteria

The current surface water standards are based on “designated use” categories, which for Lake Whatcom is “Primary Contact Recreation.” The standard for bacteria is described in Chapter 173–201A–200 of the Washington Administrative Code, Water Quality Standards for Surface Waters of the state of Washington:

Fecal coliform organism levels within an averaging period must not exceed a geometric mean value of 100 CFU or MPN per 100 mL, with not more than 10 percent of all samples (or any single sample when less than ten sample points exist) obtained within an averaging period exceeding 200 CFU or MPN per 100 mL.

All of the mid-basin (Sites 1–4) and Intake values for fecal coliforms¹⁸ were less than 10 cfu¹⁹/100 mL (Figures B116–B120, pages 216–220) and passed the freshwater *Primary Contact Recreation* bacteria standard.

¹⁶See discussion of correlation in footnote on page 6

¹⁷Dinoflagellates are small single-cell algae that are common in Lake Whatcom, but rarely have high densities in the plankton counts.

¹⁸Fecal coliforms are currently called “thermotolerant” coliforms (APHA 2017).

¹⁹Colony forming unit/100 mL; cfu/100 mL is sometimes labeled “colonies/100 mL.”

Coliform samples collected offshore from the Bloedel-Donovan swimming area had slightly higher counts than at Site 1 (mid-basin). None of the Bloedel-Donovan counts exceeded 100 cfu/100 mL and the geometric mean was 3 cfu/100 mL, so this site passed both parts of the freshwater *Primary Contact Recreation* bacteria standard.

2.3.7 Total organic carbon and disinfection by-products

Total organic carbon concentrations, along with plankton and chlorophyll data, are used to help assess the likelihood of developing potentially harmful disinfection by-products through the reaction of chlorine with organic compounds during the drinking water treatment process. Algae excrete dissolved organic carbon into water, which can react with chlorine to form disinfection by-products, predominately chloroform and other trihalomethanes (THMs). When algal densities (or total organic carbon concentrations) increase, we expect to see an increase in THMs. To minimize risk, limits are set on the levels of disinfection by-products allowed in treated drinking water through the Safe Drinking Water Act's Disinfection Byproduct Rule. This Rule was adopted in 1979 and has undergone two major revisions (Phase I in 1998; Phase II in 2005). The sampling requirement doubled under Phase II; currently the City samples eight locations in the water distribution system.²⁰

The 2018/2019 total organic carbon concentrations ranged from 1.7–2.2 mg/L (Table 2.9, page 25). The samples were split and analyzed by AmTest and the IWS laboratory to compare results. Most of the samples differed by no more than ± 0.5 mg/L (median difference = 0.1 mg/L). Larger differences could have been caused by small particulates that were unevenly distributed in the split samples or differences in the analytical methodologies.

The 2019/2019 THMs and HAAs remained below the maximum contaminant levels of 0.080 mg/L and 0.060 mg/L, respectively, described in Chapter 246–290–310 of Washington Administrative Code, Water Quality Standards for Public Water Supplies. The 1991–2015 THMs concentrations showed a significant increase over time, particularly during the spring and summer (Quarters 2–3; Figures 2.25–2.26, pages 50–51), when algal densities are higher. Since 2015, however, the THMs appear to be more stable. Haloacetic acids (HAAs), another type of dis-

²⁰P. Wendling, pers. comm., City of Bellingham Public Works Dept.

infection by-product, also increased over time, with more stable concentrations during the past 5–6 years (Figure 2.27, page 52). Only the winter and spring HAAs data followed this trend (Quarters 1–2); the summer and fall data were not significantly correlated with year (Figure 2.28, page 53). According to Sung, et al. (2000), HAAs are not as closely linked to algal concentrations and chlorine dose as THMs. In addition, HAAs can be degraded by the microbial biofilm that grows on the surface of water treatment filtration media (Baribeau, et al., 2005).

Abbrev.	Parameter	Method	Historic DL [†]	2018/2019 MDL [†]	Sensitivity or Confidence limit
IWS field measurements:					
cond	Conductivity	YSI (2017)	–	–	± 2 µS/cm
do	Dissolved oxygen	YSI (2017)	–	–	± 0.1 mg/L
ph	pH	YSI (2017)	–	–	± 0.1 pH unit
temp	Temperature	YSI (2017)	–	–	± 0.1° C
disch	Discharge	Rantz et al. (1982); SOP-IWS-6	–	–	–
secchi	Secchi depth	Lind (1985)	–	–	± 0.1 m
IWS laboratory analyses:					
alk	Alkalinity	APHA (2017) #2320; SOP-IWS-8	–	–	± 0.6 mg/L
cond	Conductivity	APHA (2017) #2510; SOP-IWS-8	–	–	± 2.1 µS/cm
do	Dissolved oxygen	APHA (2017) #4500-O.C.; SOP-IWS-8	–	–	± 0.1 mg/L
ph	pH-lab	APHA (2017) #4500-H ⁺ ; SOP-IWS-8	–	–	± 0.1 pH unit
tss	T. suspended solids	APHA (2017) #2540 D; SOP-IWS-13	2 mg/L	1.4 mg/L	± 2.6 mg/L
turb	Turbidity	APHA (2017) #2130; SOP-IWS-8	–	–	± 0.2 NTU
nh4	Ammonium (auto)	APHA (2017) #4500-NH ₃ H; SOP-IWS-19	10 µg-N/L	9.1 µg-N/L	± 11.7 µg-N/L
no3	Nitrite/nitrate (auto)	APHA (2017) #4500-NO ₃ I; SOP-IWS-22	20 µg-N/L	25.9 µg-N/L	± 21.6 µg-N/L
tn	T. nitrogen (auto)	APHA (2017) #4500-N C; SOP-IWS-22	100 µg-N/L	24.4 µg-N/L	± 28.1 µg-N/L
srp	Sol. phosphate (auto)	APHA (2017) #4500-P G; SOP-IWS-22	5 µg-P/L	4.0 µg-P/L	± 2.1 µg-P/L
tp	T. phosphorus (auto)	APHA (2017) #4500-P J; SOP-IWS-22	5 µg-P/L	1.8 µg-P/L	± 2.0 µg-P/L
toc [‡]	T. organic carbon	EPA #414.3; Potter and Wimsatt (2009)	1.0 mg/L	0.5 mg/L	–
IWS plankton analyses:					
chl	Chlorophyll	APHA (2017) #10200 H; SOP-LW-16	–	–	± 0.1 µg/L
chlo	Chlorophyta	Lind (1985), Schindler trap	–	–	–
cyan	Cyanobacteria	Lind (1985), Schindler trap	–	–	–
chry	Chrysophyta	Lind (1985), Schindler trap	–	–	–
pyrr	Pyrrophyta	Lind (1985), Schindler trap	–	–	–
City coliform analyses:					
fc	Fecal coliform [§]	APHA (2017) #9222 D	1 cfu/100 mL	1 cfu/100 mL	–
Edge Analytical analyses:					
H ₂ S	Hydrogen sulfide	APHA (2017) #4500-S2 F	–	0.100 mg/L	–
AmTest analyses:					
toc [‡]	T. organic carbon	APHA (2017) #5310 B	1.0 mg/L	0.5 mg/L	–

[†]Historic detection limits (DL) are usually higher than current method detection limits (MDL).

[‡]Total organic carbon analyses are run in duplicate by IWS and AmTest to evaluate analytical equivalence.

[§]Fecal coliforms are now called thermotolerant coliforms (APHA 2017).

Table 2.1: Summary of IWS, AmTest, Edge Analytical, and City of Bellingham analytical methods and parameter abbreviations.

Parameter	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct [†]	Nov [†]	Dec [†]	Locations [‡]
DO - field		•		•	•	•	•	•	•	•	•	•	Sites 1, 2, Intake - every 1 m;
pH - field		•		•	•	•	•	•	•	•	•	•	Sites 3, 4 - every 1 m to 10 m
Temp - field		•		•	•	•	•	•	•	•	•	•	then every 5 m; Gatehouse
Cond - field		•		•	•	•	•	•	•	•	•	•	
Secchi depth		•		•	•	•	•	•	•	•	•	•	Sites 1, 2, 3, 4, Intake
Alkalinity		•		•	•	•	•	•	•	•	•	•	Sites 1, 2 - 0.3, 5, 10, 15, 20 m;
Ammonium		•		•	•	•	•	•	•	•	•	•	Intake - 0.3, 5, 10 m;
Nitrate/nitrite		•		•	•	•	•	•	•	•	•	•	Site 3 - 0.3, 5, 10, 20, 40, 60,
T. nitrogen		•		•	•	•	•	•	•	•	•	•	80 m; Site 4 - 0.3, 5, 10, 20, 40
Sol. phosphate		•		•	•	•	•	•	•	•	•	•	60, 80, 90 m; Gatehouse
T. phosphorus		•		•	•	•	•	•	•	•	•	•	
Turbidity		•		•	•	•	•	•	•	•	•	•	
T. organic carbon		•					•						Sites 1, 2, 3, 4, Intake - 0.3 m and bottom only
Chlorophyll		•		•	•	•	•	•	•	•	•	•	Sites 1, 2, 3, 4 - 0.3, 5, 10, 15, 20 m; Intake - 0.3, 5, 10 m
Plankton		•		•	•	•	•	•	•	•	•	•	Sites 1, 2, 3, 4, Intake; 5 m
Bacteria (City)		•		•	•	•	•	•	•	•	•	•	Sites 1, 2, 3, 4, Intake, Bloedel-Donovan; 0.3 m
H ₂ S - opt										•			Sites 1, 2 - 10, 15, 20 m

[†]Samples will be collected Jan-Dec in 2019 and 2020; field work will end in September 2021 to allow time to complete all analyses unless the monitoring contract is extended past December 2021.

[‡]Samples within each parameter subgroup are collected at all locations listed in this column.

Table 2.2: Lake Whatcom annual lake monitoring summary. All field and laboratory methods are summarized in Table 2.1.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	20.0	21.3	21.8	29.3
Conductivity (μS/cm)	58.4	59.8	61.3	77.9
Dissolved oxygen (mg/L)	0.0	9.4	8.3	12.4
pH	6.4	7.2	7.3	8.8
Temperature (°C)	3.8	10.0	11.4	22.8
Turbidity (NTU)	0.5	0.8	1.1	4.0
Nitrogen, ammonium (μg-N/L)	<10	11.2	52.1	508.0
Nitrogen, nitrate/nitrite (μg-N/L)	<20	111.8	116.3	282.8
Nitrogen, total (μg-N/L)	204.3	355.9	363.1	672.7
Phosphorus, soluble (μg-P/L)	<5	<5	<5	32.8
Phosphorus, total (μg-P/L)	<5	8.0	10.2	63.9
Chlorophyll (μg/L)	0.5	3.8	3.8	15.7
Secchi depth (m)	3.4	4.2	4.7	6.5
Coliforms, fecal (cfu/100 mL) [‡]	<1	1	1	6

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 2.3: Summary of Site 1 water quality data, Oct. 2018 – Sept. 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	18.8	20.3	20.1	21.0
Conductivity (μS/cm)	56.8	57.8	57.6	59.7
Dissolved oxygen (mg/L)	8.8	10.2	10.4	12.2
pH	7.0	7.8	7.8	8.7
Temperature (°C)	6.0	15.6	14.5	21.8
Turbidity (NTU)	0.3	0.5	0.5	0.8
Nitrogen, ammonium (μg-N/L)	<10	<10	<10	22.5
Nitrogen, nitrate/nitrite (μg-N/L)	50.1	138.4	156.2	321.1
Nitrogen, total (μg-N/L)	214.6	315.3	328.7	514.4
Phosphorus, soluble (μg-P/L)	<5	<5	<5	<5
Phosphorus, total (μg-P/L)	<5	<5	<5	6.4
Chlorophyll (μg/L)	1.1	3.0	3.2	7.0
Secchi depth (m)	5.0	6.0	6.0	7.5
Coliforms, fecal (cfu/100 mL) [‡]	<1	1	1	3

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 2.4: Summary of Intake water quality data, Oct. 2018– Sept. 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	18.7	20.3	20.9	36.1
Conductivity (μS/cm)	56.8	57.7	58.9	85.0
Dissolved oxygen (mg/L)	0.0	10.0	9.1	12.2
pH	6.4	7.5	7.4	8.6
Temperature (°C)	5.3	11.4	12.6	21.7
Turbidity (NTU)	0.3	0.5	0.9	5.5
Nitrogen, ammonium (μg-N/L)	<10	<10	51.3	690.6
Nitrogen, nitrate/nitrite (μg-N/L)	<20	163.5	160.7	341.8
Nitrogen, total (μg-N/L)	212.3	359.8	389.4	950.8
Phosphorus, soluble (μg-P/L)	<5	<5	<5	17.1
Phosphorus, total (μg-P/L)	<5	5.0	7.5	40.8
Chlorophyll (μg/L)	0.6	2.8	3.0	7.2
Secchi depth (m)	4.7	6.3	6.3	8.6
Coliforms, fecal (cfu/100 mL) [‡]	<1	1	1	2

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 2.5: Summary of Site 2 water quality data, Oct. 2018 – Sept. 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	18.6	19.0	19.4	21.0
Conductivity (μ S/cm)	56.2	57.0	57.5	131.2
Dissolved oxygen (mg/L)	0.1	10.1	10.0	12.2
pH	6.5	7.1	7.3	8.9
Temperature (°C)	6.1	7.4	10.4	22.2
Turbidity (NTU)	0.0	0.4	0.4	2.2
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	38.4
Nitrogen, nitrate/nitrite (μ g-N/L)	53.8	309.2	265.4	419.9
Nitrogen, total (μ g-N/L)	242.0	427.3	416.3	574.6
Phosphorus, soluble (μ g-P/L)	<5	<5	<5	6.0
Phosphorus, total (μ g-P/L)	<5	<5	<5	12.6
Chlorophyll (μ g/L)	0.9	3.0	3.2	9.6
Secchi depth (m)	3.9	6.4	6.3	8.7
Coliforms, fecal (cfu/100 mL) [‡]	<1	1	1	2

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 2.6: Summary of Site 3 water quality data, Oct. 2018 – Sept. 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	18.5	18.9	19.2	20.9
Conductivity (μS/cm)	55.8	56.9	56.9	58.3
Dissolved oxygen (mg/L)	8.3	10.0	10.1	12.2
pH	6.4	6.9	7.2	8.6
Temperature (°C)	6.1	6.9	10.1	21.7
Turbidity (NTU)	0.2	0.3	0.4	1.0
Nitrogen, ammonium (μg-N/L)	<10	<10	<10	19.9
Nitrogen, nitrate/nitrite (μg-N/L)	69.4	317.4	279.8	411.3
Nitrogen, total (μg-N/L)	214.3	423.9	410.0	514.4
Phosphorus, soluble (μg-P/L)	<5	<5	<5	<5
Phosphorus, total (μg-P/L)	<5	<5	<5	21.0
Chlorophyll (μg/L)	0.6	2.1	2.7	10.4
Secchi depth (m)	3.5	6.2	6.0	7.2
Coliforms, fecal (cfu/100 mL) [‡]	<1	1	1	3

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 2.7: Summary of Site 4 water quality data, Oct. 2018 – Sept. 2019.

Year	H ₂ S (mg/L)		Year	H ₂ S (mg/L)	
	Site 1	Site 2		Site 1	Site 2
1999 [†]	0.03–0.04	0.40	2010	0.38	0.40
2000 [†]	0.27	0.53	2011	0.12	0.16
2001 [†]	0.42	0.76	2012	na	na
2002 [†]	0.09	0.32	2013	0.20 [§]	0.16
2003 [†]	0.05	0.05	2014	0.28	0.66
2004 [†]	0.25	0.25	2015	0.51	0.41
2005 [‡]	0.13, 0.12	0.25, 0.42	2016	0.64	0.51
2006	0.20	0.42	2017	0.68*	<0.05
2007	0.40	0.20	2018	0.32	0.39
2008	0.28	0.38	2019	0.10	0.22
2009	0.15	0.47			

[†]H₂S samples analyzed by HACH test kit.

[‡]HACH (first value) vs. Edge Analytical (second value)

[§]Corrected value (1.20 in Matthews, et al., 2015)

*Sample collected at 15 meters; sample from 20 m contained sediment.

Table 2.8: October hypolimnetic hydrogen sulfide concentrations at Sites 1 and 2 (20 m). The H₂S samples have been analyzed by Edge Analytical since 2005. Earlier samples were analyzed using a HACH field test kit. The 2012 samples were lost during processing.

Site	Depth (m)	Date	AmTest TOC (mg/L)	IWS TOC (mg/L)	Date	AmTest TOC (mg/L)	IWS TOC (mg/L)
Site 1	0	Feb 15, 2019	1.9	1.8	July 11, 2019	2.7	2.2
	20	Feb 15, 2019	2.0	1.8	July 11, 2019	2.3	2.0
Intake	0	Feb 15, 2019	1.8	1.7	July 11, 2019	2.3	2.0
	10	Feb 15, 2019	1.8	1.7	July 11, 2019	2.4	2.0
Site 2	0	Feb 15, 2019	1.8	1.7	July 11, 2019	2.3	2.2
	20	Feb 15, 2019	1.8	1.7	July 11, 2019	2.3	2.2
Site 3	0	Feb 15, 2019	1.8	1.7	July 9, 2019	2.3	2.1
	80	Feb 15, 2019	1.7	1.7	July 9, 2019	2.4	2.2
Site 4	0	Feb 15, 2019	1.7	1.7	July 9, 2019	2.5	1.9
	90	Feb 15, 2019	1.7	1.7	July 9, 2019	1.8	1.6

Table 2.9: Lake Whatcom 2018/2019 total organic carbon data. February and July samples were split and analyzed by Amtest (TOC-AM) and IWS (TOC-IWS).




Figure 2.1: October 2018 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2018 data.




Figure 2.2: November 2018 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2018 data.




Figure 2.3: December 2018 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2018 data.




Figure 2.4: February 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data.




Figure 2.5: April 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data.




Figure 2.6: May 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data.




Figure 2.7: June 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data.




Figure 2.8: July 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data.




Figure 2.9: August 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data. The 80 meter sample from Site 3 has been omitted because it was collected too close to the lake bottom and may not reflect water column conditions.




Figure 2.10: September 2019 temperature (---●---) and dissolved oxygen (---●---) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data. The 80 meter sample from Site 3 has been omitted because it was collected too close to the lake bottom and may not reflect water column conditions




Figure 2.11: October 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data. October 2019 is not part of the 2018/2019 sampling period, but were included to to provide information on the timing of destratification.




Figure 2.12: November 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data. November 2019 is not part of the 2018/2019 sampling period, but were included to to provide information on the timing of destratification.




Figure 2.13: December 2019 temperature (-●-) and dissolved oxygen (-●-) profiles compared to historic ranges. The gradation in shading shows the approximate frequency of the 1988–2019 data. December 2019 is not part of the 2018/2019 sampling period, but were included to to provide information on the timing of destratification.




Figure 2.14: Relationship between dissolved oxygen and time at Site 1, 12 m. Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.15: Relationship between dissolved oxygen and time at Site 1, 14 m. Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.16: Relationship between dissolved oxygen and time at Site 1, 16 m. Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.17: Relationship between dissolved oxygen and time at Site 1, 18 m. Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.18: Minimum summer, near-surface dissolved inorganic nitrogen (DIN) concentrations (1994–2019 June–Oct, depths ≤ 5 m). Uncensored (raw) data were used to illustrate that minimum values are dropping below analytical detection limits (dashed red line). Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.19: Comparison of median spring (Feb-May) vs. summer (June-Oct) near-surface dissolved inorganic nitrogen (DIN) concentrations (1994–2019, depths ≤ 5 m). Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.20: Differences between median spring (Feb-May) and summer (June-Oct) near-surface dissolved inorganic nitrogen (DIN) concentrations (1994–2019, depths ≤ 5 m; DIN difference = $DIN_{spring} - DIN_{summer}$). Kendall's τ correlations were used because the data were not monotonic-linear; correlations were marginally significant (p-value < 0.05) or not significant (p-value > 0.05).




Figure 2.21: Median summer, near-surface total phosphorus concentrations (1994–2019, June–Oct, depths ≤ 5 m). Uncensored (raw) data were used to illustrate that median values are increasingly above analytical detection limits (dashed red line). Kendall's τ correlations were used because the data were not monotonic-linear; none of the correlations were significant.




Figure 2.22: Median summer near-surface chlorophyll concentrations (1994–2019, June–October, depths ≤ 5 m). Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.23: Log₁₀ plots of median summer, near-surface algae counts (1994-2019, June-October, all sites and depths). Kendall's τ correlations were used because the data were not monotonic-linear; all correlations except Dinoflagellates were significant. Note difference in vertical axis scales.





Figure 2.24: Log₁₀ plots of median summer, near-surface Cyanobacteria counts (1994–2019, June–October, depths ≤5 m). Kendall’s τ correlations were used because the data were not monotonic-linear; all correlations were significant.






Figure 2.26: Total total trihalomethanes (THMs) quarterly average concentrations in the Bellingham water distribution system plotted by quarter (data provided by the City of Bellingham Public Works Department). The recommended maximum contaminant level for total THMs is 0.080 mg/l; all samples were below the level. The number of sites used to calculate the quarterly averages increased from four to eight in the fourth quarter of 2012 (vertical red line). Kendall's τ correlations were used because the data were not monotonic-linear; all correlations were significant.




Figure 2.27: Haloacetic acids (HAAs) quarterly average concentrations in the Bellingham water distribution system (data provided by the City of Bellingham Public Works Department). The recommended maximum contaminant level for HAAs is 0.060 mg/l; all samples were below the level. The number of sites used to calculate the quarterly averages increased from four to eight in the fourth quarter of 2012 (vertical red line). Kendall's τ correlation was used because the data were not monotonic-linear; the correlation was significant.




Figure 2.28: Haloacetic acids (HAAs) quarterly average concentrations in the Bellingham water distribution system plotted by quarter (data provided by the City of Bellingham Public Works Department). The recommended maximum contaminant level for HAAs is 0.060 mg/l; all samples were below the level. The number of sites used to calculate the quarterly averages increased from four to eight in the fourth quarter of 2012 (vertical red line). Kendall's τ correlations were used because the data were not monotonic-linear; the Quarter 1 and Quarter 2 correlations were significant.

3 Tributary Monitoring

The major objective for the tributary monitoring was to provide baseline water quality data for the tributaries that flow into Lake Whatcom. Whatcom Creek was also sampled to provide baseline data for the lake's outlet. Monthly samples were collected in 2004–2006, 2010–2012, and 2014. The level of effort was reduced in 2007–2009, with samples collected twice each year. Monthly sampling was re-initiated in January 2016 and has continued through 2019.

3.1 Site Descriptions

Samples were collected from Anderson, Austin, Blue Canyon, Brannian, Carpenter, Euclid, Millwheel, Olsen, Silver Beach, Smith, and Whatcom Creeks and the Park Place drain. The sampling locations for these sites are described in Appendix A.2 and shown on Figure A2, page 96.

3.2 Field Sampling and Analytical Methods

The tributaries were sampled on October 9, November 13, and December 11, 2018; and January 15, February 19, March 12, April 23, May 14, June 12, July 16, August 13, and September 4, 2019. All samples were collected during daylight hours, typically between 10:00 am and 3:00 pm. The analytical and sampling procedures are summarized in Tables 2.1 & 3.1 (pages 17 & 59).

A YSI ProDO LDO field meter was used to measure temperature and dissolved oxygen in the field. Raw water and bacteriological samples were stored on ice and in the dark until they reached the laboratory. The bacteria samples were analyzed by the City of Bellingham and total organic carbon analyses were analyzed by AmTest²¹ and by IWS.

²¹AmTest, 13600 Northeast 126th Place, Suite C, Kirkland, WA, 98034–8720.

3.3 Results and Discussion

The tributary data include field measurements (dissolved oxygen and temperature); laboratory analyses for ambient water quality parameters (ammonium,²² nitrate/nitrite,²³ total nitrogen, soluble phosphate, total phosphorus, alkalinity, conductivity, pH, total suspended solids, and turbidity); bacteria counts; and total organic carbon measurements.

The 2018–2019 tributary data are summarized in Table 3.2 (page 60), with descriptive statistics for each site listed in Tables 3.3–3.14 (pages 61–72). The total organic carbon data are listed in Table 3.15 (page 73). During the summer the stream flow was too low to collect samples at five sites: Brannian, Carpenter and Millwheel Creeks were not sampled in August and September 2019; Euclid Creek was not sampled in October 2018 and from June through September 2019; Silver Beach Creek was not sampled in September 2019. As a result, the summary statistics for these sites are biased toward water quality conditions present during spring and winter.

Historic tributary data from 2004 to the present are plotted in Appendix B.4 (Figures B131–B169, pages 233–271). These figures include a dashed (blue) horizontal line that shows the median value for Smith Creek and a solid (red) horizontal line that shows the median value for each site. Smith Creek was chosen as a reference because it is a major tributary to the lake and has a history of being relatively unpolluted.

In Table 3.2, the “typical ranges” for alkalinity, conductivity, total suspended solids, ammonium, and soluble phosphate were derived from historic water quality data for Lake Whatcom tributaries that flow through predominantly forested portions of the watershed (Anderson, Brannian, Olsen, and Smith Creeks). The temperature, dissolved oxygen, and pH ranges were based on WAC 173-201A, Tables 200 (1)(c) and 200 (1)(g) for salmonid spawning, rearing, and migration, with the qualification that the single monthly grab samples from the Lake What-

²²Ammonium (NH_4^+) is ionized ammonia (NH_3). Nearly all ammonia is ionized in surface water. Earlier IWS reports used the term ammonia and ammonium interchangeably to describe ammonium concentrations because it is generally understood that ammonia is usually ionized. To improve clarity, IWS has switched to the term “ammonium” to indicate that we are reporting the concentration of ionized ammonia. This does not represent any change in analytical methods.

²³Nitrate and nitrite were analyzed together because nitrite concentrations are very low in surface water and require low level analytical techniques to measure accurately. For simplicity, nitrate/nitrite will be referred to as “nitrate” in this document.

com tributaries may not show the lowest 1-day minimum dissolved oxygen or the maximum 7-day temperature. The turbidity range was based on historic watershed data and WAC 173-201A Table 200 (1)(e), which limits anthropogenic contributions to no more than 5 NTU over background. The coliform range was based on WAC 173-201A Table 200 (2)(b) for primary contact recreation. The total phosphorus range was based on the lake nutrient criteria action value for the Coast Range, Puget Lowlands, and Northern Rockies Ecoregions listed from WAC 173-201A-230, Table 230(1). The lake nutrient criteria require collecting multiple samples from the epilimnion during summer, so the total phosphorus range in Table 3.2 can only be used as a general reference.

Water temperatures and dissolved oxygen concentrations followed typical seasonal cycles, with most sites having colder temperatures and higher oxygen concentrations during the winter, and warmer temperatures and lower oxygen concentrations during the summer (Figures B131–B136). Whatcom Creek had higher temperatures and slightly lower oxygen concentrations than most other sites, reflecting the influence of Lake Whatcom (Figures B131 and B134). The residential tributaries (Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain) often have slightly elevated temperatures and lower dissolved oxygen concentrations (Figures B133 and B136). But the dry conditions meant that some of the residential sites could not be sampled during late summer when high temperatures and low oxygen concentrations are most common.

Most of the tributaries in the Lake Whatcom watershed had relatively low concentrations of dissolved solids, indicated by conductivities $\leq 100 \mu\text{S}$ and alkalinities $\leq 25 \text{ mg/L}$ (Table 3.2; Figures B137–B145). Sites that did not match this description included the residential tributaries (Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain) and Blue Canyon Creek, which drains an area rich in soluble minerals. Most sites also had low total suspended solids concentrations ($\leq 5 \text{ mg/L}$) and low turbidities ($\leq 5 \text{ NTU}$) except during periods of high precipitation and runoff (Figures B146–B151). The only site that had consistently high solids and turbidity values was Millwheel Creek, which is often turbid due to disturbed sediments in an upstream pond.

The median ammonium concentrations were generally low ($\leq 10 \mu\text{g-N/L}$) except in the residential streams (Table 3.2; Figures B152–B154). Ammonium does not persist long in oxygenated surface waters. When present in streams, it usually indicates a near-by source such as an upstream wetland with anaerobic soils or a pollution source.

Most of the tributaries had lower total nitrogen and nitrate concentrations than Smith Creek (Figures B155– B160). The relatively high nitrate and total nitrogen concentrations in Smith Creek are probably due to the presence of nitrogen-fixing alders (*Alnus rubra*) in the riparian zone upstream from the sampling site. High nitrate and total nitrogen concentrations are not necessarily an indication of water pollution, and low nitrate concentrations actually favor the growth of nuisance Cyanobacteria. The exceptionally low nitrate concentrations in Whatcom Creek (Figure B155) reflect algal uptake of nitrogen in the lake.

Soluble inorganic phosphate is quickly removed from surface water by biota, so high concentrations of soluble phosphate usually indicate a near-by source such as an anaerobic wetland or a pollution source. The median 2018–2019 soluble phosphate concentrations were $\leq 10 \mu\text{g-P/L}$ at all sites except Millwheel and Silver Beach Creeks and the Park Place drain (Table 3.2). The historic data indicate that although soluble phosphate concentrations were generally low, nearly all sites have had a few high peaks, and high concentrations were common in residential streams.

Total phosphorus concentrations were higher than soluble phosphate concentrations (Figures B161–B166). The median 2018–2019 concentrations were $\leq 20 \mu\text{g-P/L}$ at all sites except Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain (Table 3.2). As with soluble phosphate, nearly all sites have had occasional high total phosphorus peaks.

High coliform counts are an indicator of residential pollution (Table 3.2; Figures B167–B169). Although most of the sites had relatively low coliform counts during 2018–2019, three sites exceeded a geometric mean of 100 cfu/100 mL (Millwheel and Silver Beach Creeks and the Park Place drain). Five sites (Brannian, Blue Canyon, Carpenter, Smith, and Whatcom Creeks) had more than 10% of the samples that exceeded 200 cfu/100 mL. Several of the small residential tributaries could not be sampled during the late summer, when coliform counts are often higher, so these sites may have exceeded the coliform criteria by a greater margin than what is indicated in the summary tables.

The total organic carbon concentrations from February and July 2019 are included in Table 3.15 (page 73). The residential sites (Carpenter, Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain) had slightly elevated ($\geq 3 \text{ mg/L}$) total organic carbon concentrations. The paired samples analyzed by IWS and Amtest were very similar, with most samples differing by $< 0.5 \text{ mg/L}$ (median

difference = 0.3 mg/L). Larger differences could have been caused by small particulates that were unevenly distributed in the split samples or differences in analytical methodologies. The samples from July were slightly more variable than February, but this may have been related to low flow conditions that made it difficult to collect samples that did not contain suspended organic particulates.

Parameter	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
DO -field	•	•	•	•	•	•	•	•	•	•	•	•
pH - lab	•	•	•	•	•	•	•	•	•	•	•	•
Temp - field	•	•	•	•	•	•	•	•	•	•	•	•
Cond - lab	•	•	•	•	•	•	•	•	•	•	•	•
Alkalinity	•	•	•	•	•	•	•	•	•	•	•	•
Ammonium	•	•	•	•	•	•	•	•	•	•	•	•
Nitrate/nitrite	•	•	•	•	•	•	•	•	•	•	•	•
T. nitrogen	•	•	•	•	•	•	•	•	•	•	•	•
Sol. phosphate	•	•	•	•	•	•	•	•	•	•	•	•
T. phosphorus	•	•	•	•	•	•	•	•	•	•	•	•
T. susp. solids	•	•	•	•	•	•	•	•	•	•	•	•
Turbidity	•	•	•	•	•	•	•	•	•	•	•	•
T. organic carbon	•	•	•	•	•	•	•	•	•	•	•	•
Bacteria (City)	•	•	•	•	•	•	•	•	•	•	•	•

Table 3.1: Lake Whatcom monthly tributary monitoring summary. All field and laboratory methods are summarized in Table 2.1.

	Typical range	Anderson	Austin	Brannian	Olsen	Smith	Whatcom
Alkalinity	med. ≤ 30 mg/L	yes	yes	yes	yes	yes	yes
Conductivity	med. ≤ 100 μ S	yes	yes	yes	yes	yes	yes
D. oxygen [†]	min. ≥ 8.0 mg/L	yes	yes	no	yes	yes	yes
pH	6.5–8.5	yes	yes	yes	yes	yes	yes
Temperature [†]	max. ≤ 17.5 C	yes	yes	yes	yes	yes	no
T. susp. solids	med. ≤ 5 mg/L	yes	yes	yes	yes	yes	yes
Turbidity	med. ≤ 5 NTU	yes	yes	yes	yes	yes	yes
Ammonium	med. ≤ 10 μ g-N/L	yes	yes	yes	yes	yes	yes
Sol. phosphate	med. ≤ 10 μ g-P/L	yes	yes	yes	yes	yes	yes
T. phosphorus	med. ≤ 20 μ g-P/L	yes	yes	yes	yes	yes	yes
F. coliforms	gmean ≤ 100 cfu	yes	yes	yes	yes	yes	yes
	max. 10% > 200 cfu	no	no	yes	no	yes	yes

	Typical range	Blue Canyon	Carpenter	Euclid	Mill- wheel	Park Place	Silver Beach
Alkalinity	med. ≤ 30 mg/L	no	yes	yes	no	no	no
Conductivity	med. ≤ 100 μ S	no	yes	no	no	no	no
D. oxygen [†]	min. ≥ 8.0 mg/L	yes	yes	yes	no	no	yes
pH	6.5–8.5	yes	yes	yes	yes	yes	yes
Temperature [†]	max. ≤ 17.5 C	yes	yes	yes	no	no	yes
T. susp. solids	med. ≤ 5 mg/L	yes	yes	no	no	yes	yes
Turbidity	med. ≤ 5 NTU	yes	yes	yes	no	yes	yes
Ammonium	med. ≤ 10 μ g-N/L	yes	yes	yes	no	no	yes
Sol. phosphate	med. ≤ 10 μ g-P/L	yes	yes	yes	no	no	no
T. phosphorus	med. ≤ 20 μ g-P/L	yes	yes	no	no	no	no
F. coliforms	gmean ≤ 100 cfu	yes	yes	yes	no	no	no
	Max. 10% > 200 cfu	yes	yes	no	no	no	no

[†]Many of the residential creeks were not sampled during part of the summer due to low flow, which is when water temperatures are usually high and dissolved oxygen concentrations low.

Table 3.2: Comparison of October 2018-September 2019 water quality in Lake Whatcom tributaries (“no” indicates that the site does not fall within the water quality ranges or meet the criteria described on page 55).

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	14.7	18.4	19.2	24.3
Conductivity (μ S/cm)	45.3	55.6	56.4	69.0
Dissolved oxygen (mg/L)	9.0	10.8	10.6	12.5
pH	6.7	6.9	6.9	7.0
Temperature ($^{\circ}$ C)	3.8	9.5	9.8	16.7
Total suspended solids (mg/L)	<2	<2	2.8	19.7
Turbidity (NTU)	0.4	1.0	2.0	12.2
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	18.6
Nitrogen, nitrate/nitrite (μ g-N/L)	35.7	335.0	300.5	491.5
Nitrogen, total (μ g-N/L)	152.5	455.0	463.5	750.7
Phosphorus, soluble (μ g-P/L)	5.6	7.9	7.8	11.7
Phosphorus, total (μ g-P/L)	7.9	15.4	18.1	47.5
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 17)	3	25	34	350

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.3: Summary of Anderson Creek water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	14.8	22.5	25.6	42.5
Conductivity (μ S/cm)	53.5	82.2	92.4	153.0
Dissolved oxygen (mg/L)	9.4	11.3	11.4	13.3
pH	7.3	7.5	7.5	7.7
Temperature ($^{\circ}$ C)	3.1	9.9	9.5	15.4
Total suspended solids (mg/L)	<2	<2	8.4	52.0
Turbidity (NTU)	0.5	1.1	7.3	60.1
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	20.8
Nitrogen, nitrate/nitrite (μ g-N/L)	185.3	425.2	411.9	769.2
Nitrogen, total (μ g-N/L)	284.0	558.8	563.5	911.3
Phosphorus, soluble (μ g-P/L)	5.0	6.7	7.1	12.5
Phosphorus, total (μ g-P/L)	6.9	12.8	18.0	49.1
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 25)	3	78	68	560

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.4: Summary of Austin Creek water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	121.8	146.7	156.6	189.9
Conductivity (μ S/cm)	261.0	324.5	322.4	360.0
Dissolved oxygen (mg/L)	9.9	11.2	11.3	12.9
pH	8.2	8.4	8.4	8.5
Temperature ($^{\circ}$ C)	4.1	10.0	10.0	15.5
Total suspended solids (mg/L)	<2	2.7	4.9	21.5
Turbidity (NTU)	0.5	1.6	2.5	10.6
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	37.2
Nitrogen, nitrate/nitrite (μ g-N/L)	136.1	348.5	373.9	776.3
Nitrogen, total (μ g-N/L)	210.5	473.7	500.1	1021.5
Phosphorus, soluble (μ g-P/L)	<5	6.9	7.1	14.9
Phosphorus, total (μ g-P/L)	5.4	10.9	13.5	30.0
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 8)	<1	6	11	1400

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.5: Summary of Blue Canyon Creek water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	8.2	9.6	12.6	21.3
Conductivity (μ S/cm)	33.6	38.5	41.9	60.4
Dissolved oxygen (mg/L)	7.0	11.6	10.6	13.1
pH	6.6	6.9	6.9	7.1
Temperature ($^{\circ}$ C)	3.2	7.7	8.3	14.8
Total suspended solids (mg/L)	<2	<2	4.4	29.5
Turbidity (NTU)	0.2	1.0	2.6	13.8
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	<10
Nitrogen, nitrate/nitrite (μ g-N/L)	84.7	453.3	404.9	748.4
Nitrogen, total (μ g-N/L)	188.1	534.7	530.9	891.3
Phosphorus, soluble (μ g-P/L)	<5	<5	<5	5.7
Phosphorus, total (μ g-P/L)	<5	6.6	12.1	54.6
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 10)	1	17	17	360

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.6: Summary of Brannian Creek water quality data, October 2018-September 2019. This site was not sampled in August and September 2019 due to low flow.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	16.7	21.9	30.0	52.3
Conductivity (μ S/cm)	60.0	69.5	83.1	123.3
Dissolved oxygen (mg/L)	9.4	11.8	11.7	13.4
pH	7.3	7.5	7.6	7.8
Temperature ($^{\circ}$ C)	2.6	7.7	8.2	16.7
Total suspended solids (mg/L)	<2	<2	3.1	7.6
Turbidity (NTU)	0.6	1.6	2.5	7.3
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	17.8
Nitrogen, nitrate/nitrite (μ g-N/L)	38.2	692.2	599.5	1043.5
Nitrogen, total (μ g-N/L)	205.9	933.4	819.8	1263.0
Phosphorus, soluble (μ g-P/L)	<5	6.8	7.6	12.7
Phosphorus, total (μ g-P/L)	7.4	18.4	16.8	28.0
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 10)	5	80	65	310

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.7: Summary of Carpenter Creek water quality data, October 2018-September 2019. This site was not sampled in August and September 2019 due to low flow.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	21.3	26.9	29.2	44.2
Conductivity (μS/cm)	73.6	111.3	123.0	235.8
Dissolved oxygen (mg/L)	9.4	11.4	11.2	12.7
pH	7.1	7.2	7.3	7.4
Temperature (°C)	4.2	7.2	7.2	11.3
Total suspended solids (mg/L)	<2	6.2	10.9	34.0
Turbidity (NTU)	0.5	4.6	7.6	16.8
Nitrogen, ammonium (μg-N/L)	<10	<10	<10	32.7
Nitrogen, nitrate/nitrite (μg-N/L)	387.7	634.5	629.1	1139.6
Nitrogen, total (μg-N/L)	611.8	768.9	885.1	1348.3
Phosphorus, soluble (μg-P/L)	<5	5.6	6.6	9.3
Phosphorus, total (μg-P/L)	5.7	27.4	30.5	75.6
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 29)	2	35	32	390

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 3.8: Summary of Euclid Creek water quality data, October 2018-September 2019. This site was not sampled in October 2018 and June-September 2019 due to low flow.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	20.2	34.9	41.3	72.3
Conductivity (μS/cm)	76.0	126.2	120.4	172.4
Dissolved oxygen (mg/L)	1.2	9.8	8.9	12.6
pH	7.0	7.2	7.2	7.6
Temperature (°C)	3.4	9.3	11.3	23.3
Total suspended solids (mg/L)	3.5	10.0	19.6	80.0
Turbidity (NTU)	4.2	9.7	15.1	58.7
Nitrogen, ammonium (μg-N/L)	<10	10.8	55.4	291.0
Nitrogen, nitrate/nitrite (μg-N/L)	<20	500.6	431.9	1160.8
Nitrogen, total (μg-N/L)	690.9	1074.2	1292.8	3034.4
Phosphorus, soluble (μg-P/L)	6.4	11.8	15.7	52.4
Phosphorus, total (μg-P/L)	21.1	63.9	214.1	1342.0
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 70)	14	295	185	610

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 3.9: Summary of Millwheel Creek water quality data, October 2018-September 2019. This site was not sampled in August and September 2019 due to low flow.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	15.7	26.5	32.7	55.5
Conductivity (μ S/cm)	50.2	76.3	87.2	134.4
Dissolved oxygen (mg/L)	9.8	11.4	11.5	13.7
pH	7.4	7.6	7.7	7.9
Temperature ($^{\circ}$ C)	2.2	9.4	9.3	16.1
Total suspended solids (mg/L)	<2	<2	3.3	8.5
Turbidity (NTU)	0.3	1.4	2.0	7.2
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	19.0
Nitrogen, nitrate/nitrite (μ g-N/L)	259.7	626.0	599.5	1167.6
Nitrogen, total (μ g-N/L)	357.0	802.4	754.9	1382.6
Phosphorus, soluble (μ g-P/L)	5.3	8.8	8.2	12.8
Phosphorus, total (μ g-P/L)	6.6	13.6	14.3	22.0
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 17)	4	64	46	830

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.10: Summary of Olsen Creek water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	40.7	73.5	79.5	120.3
Conductivity (μ S/cm)	113.6	226.6	247.8	471.0
Dissolved oxygen (mg/L)	7.7	10.2	10.0	12.4
pH	7.3	7.5	7.6	8.1
Temperature ($^{\circ}$ C)	4.6	12.1	12.7	20.5
Total suspended solids (mg/L)	<2	<2	4.4	14.0
Turbidity (NTU)	0.7	3.5	6.0	19.0
Nitrogen, ammonium (μ g-N/L)	<10	15.4	70.2	693.3
Nitrogen, nitrate/nitrite (μ g-N/L)	122.2	404.4	499.7	1064.7
Nitrogen, total (μ g-N/L)	404.3	692.0	933.5	3015.3
Phosphorus, soluble (μ g-P/L)	7.5	23.2	29.5	111.8
Phosphorus, total (μ g-P/L)	18.1	39.6	52.8	221.6
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 50)	<1	183	117	4000

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.11: Summary of Park Place outlet water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	48.7	91.3	85.8	125.2
Conductivity (μ S/cm)	139.0	218.9	211.6	293.8
Dissolved oxygen (mg/L)	9.4	11.2	11.2	13.0
pH	7.8	7.9	7.9	8.2
Temperature ($^{\circ}$ C)	3.6	10.3	9.4	16.2
Total suspended solids (mg/L)	<2	3.4	4.1	13.0
Turbidity (NTU)	1.4	3.3	3.9	7.2
Nitrogen, ammonium (μ g-N/L)	<10	<10	<10	17.7
Nitrogen, nitrate/nitrite (μ g-N/L)	203.1	558.1	563.3	909.2
Nitrogen, total (μ g-N/L)	520.2	877.9	873.3	1201.2
Phosphorus, soluble (μ g-P/L)	9.9	11.0	15.0	22.7
Phosphorus, total (μ g-P/L)	13.6	33.5	31.9	46.0
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 36)	40	130	166	1100

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.12: Summary of Silver Beach Creek water quality data, October 2018-September 2019. This site was not sampled in September 2019 due to low flow.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	15.6	20.5	24.5	40.5
Conductivity (μS/cm)	50.3	62.0	70.0	105.5
Dissolved oxygen (mg/L)	9.7	11.6	11.6	13.8
pH	7.3	7.5	7.5	7.8
Temperature (°C)	2.6	9.2	9.2	15.2
Total suspended solids (mg/L)	<2	<2	<2	3.2
Turbidity (NTU)	0.2	0.7	0.8	1.9
Nitrogen, ammonium (μg-N/L)	<10	<10	<10	10.7
Nitrogen, nitrate/nitrite (μg-N/L)	268.8	883.2	727.7	1181.7
Nitrogen, total (μg-N/L)	327.4	978.9	851.6	1368.6
Phosphorus, soluble (μg-P/L)	<5	5.5	5.5	6.7
Phosphorus, total (μg-P/L)	<5	7.8	7.8	11.2
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 8)	1	11	15	220

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 ⇒ 1).

Table 3.13: Summary of Smith Creek water quality data, October 2018-September 2019.

Variable	Min.	Med.	Mean [†]	Max.
Alkalinity (mg/L CaCO ₃)	20.3	22.1	21.8	23.1
Conductivity (μ S/cm)	59.0	61.2	62.3	68.6
Dissolved oxygen (mg/L)	9.0	9.9	10.5	12.6
pH	7.3	7.5	7.6	7.9
Temperature ($^{\circ}$ C)	4.1	14.7	14.4	23.5
Total suspended solids (mg/L)	<2	<2	2.1	5.6
Turbidity (NTU)	0.6	1.0	1.2	3.2
Nitrogen, ammonium (μ g-N/L)	<10	10.0	10.7	65.8
Nitrogen, nitrate/nitrite (μ g-N/L)	<20	110.5	129.8	334.8
Nitrogen, total (μ g-N/L)	221.5	345.7	360.9	506.0
Phosphorus, soluble (μ g-P/L)	<5	<5	<5	<5
Phosphorus, total (μ g-P/L)	6.6	8.7	9.8	18.2
Coliforms, fecal (cfu/100 mL) [‡] (Percent of samples >200 cfu/100 mL = 0)	1	9	11	56

[†]Uncensored arithmetic means except coliforms (geometric mean);

[‡]Censored values replaced with closest integer (i.e., <1 \Rightarrow 1).

Table 3.14: Summary of Whatcom Creek water quality data, October 2018-September 2019.

Site	Date	TOC-AM (mg/L)	TOC-IWS (mg/L)	Date	TOC-AM (mg/L)	TOC-IWS (mg/L)
Anderson	Feb 19, 2019	2.5	2.3	Jul 16, 2019	2.3	1.9
Austin (lower)	Feb 19, 2019	2.2	2.1	Jul 16, 2019	4.6	2.5
Blue Canyon	Feb 19, 2019	2.9	2.6	Jul 16, 2019	2.5	1.6
Brannian	Feb 19, 2019	1.7	1.7	Jul 16, 2019	1.9	1.5
Carpenter	Feb 19, 2019	3.8	3.5	Jul 16, 2019	3.2	2.9
Euclid	Feb 19, 2019	3.5	2.6	Jul 16, 2019	(dry)	(dry)
Millwheel	Feb 19, 2019	3.5	3.1	Jul 16, 2019	13.0	7.9
Olsen	Feb 19, 2019	2.7	2.6	Jul 16, 2019	3.1	2.8
Park Place	Feb 19, 2019	3.5	3.2	Jul 16, 2019	4.8	3.8
Silver Beach	Feb 19, 2019	4.3	4.3	Jul 16, 2019	6.2	5.4
Smith	Feb 19, 2019	2.7	2.5	Jul 16, 2019	3.3	2.7
Whatcom	Feb 19, 2019	2.1	1.9	Jul 16, 2019	3.1	2.4

Table 3.15: Lake Whatcom 2019 tributary total organic carbon data. February and August samples were split and analyzed by Amtest (TOC-AM) and IWS (TOC-IWS).

4 Storm Water Monitoring

4.1 Hydrograph Monitoring

Recording hydrographs are installed in Austin Creek and Smith Creek; the data are plotted in Figures 4.1–4.2 (pages 79–80). The location of each hydrograph is described in Appendix A.2 (page 91). All hydrograph data, including data from previous years, are online at www.wwu.edu/iws. Field notes, comments on missing data, and rating curves for each water year are available upon request to the City of Bellingham or Institute for Watershed Studies. The rating curves were generated using Aquarius rating curve software (Aquatic Informatics, 2014; <https://aquaticinformatics.com>). The field discharge and stage height measurements are plotted in Figures 4.3–4.4 (pages 81–82) and the Aquarius rating curve equations are listed in Tables 4.1–4.2 (pages 76–77). All results are reported as Pacific Standard Time, without Daylight Saving Time adjustment.

4.2 Site Descriptions

The 2018/2019 storm water sampling focused on Austin, Euclid, and Silver Beach Creeks (Figure A2, page 96). The Euclid site is a new storm water sampling location that is located where the Euclid Creek tributary grab samples are collected monthly. Earlier storm water sampling in Austin and Silver Beach Creeks was summarized in previous annual reports (see Section 5.2, page 87).

4.3 Field Sampling and Analytical Methods

Four storm events were sampled in Austin Creek, seven events were sampled in Euclid Creek, and six events were sampled in Silver Beach Creek (Table 4.3, page 78). The samples were collected using time-paced ISCO automated samplers provided by the City of Bellingham and were analyzed for total suspended solids, total phosphorus, soluble reactive phosphorus, total nitrogen, and nitrate/nitrite²⁴ as described in Table 2.1 (page 17).

²⁴Nitrate and nitrite were analyzed together because nitrite concentrations are very low in surface water and require low level analytical techniques to measure accurately. For simplicity, nitrate/nitrite will be referred to as “nitrate” in this document.

Dry summers have a direct impact on stream flow (base flow), which is supported by soil water and groundwater. As illustrated in the hydrographs for the Lake Whatcom watershed (Figures 4.1–4.2, pages 79–80), stream discharge decreased over the course of the summer as soils dried out and groundwater levels declined due to low rainfall and high levels of evapotranspiration from vegetation. Moreover, most late summer rainfall goes into replenishing soil water (storage) rather than direct runoff into streams. Lower summer stream flows and groundwater levels will also reduce runoff into the lake. When coupled with higher summer lake withdrawals and lake evaporation, the lake level will usually drop over the course of the summer, reaching a minimum in late fall.

As indicated in Section 3 (page 54), many of the smaller tributaries to Lake Whatcom were dry, or nearly dry during late summer. As a result, all of the storm water samples described in this report were collected from October-January in 2018 or 2019. Storm water data are used by the City as part of their watershed modeling program and will be reported directly to the City to be incorporated into the model. Storm water data are available upon request to the City of Bellingham or the Institute for Watershed Studies.

Stage Height (ft)	Discharge Equations
0.25–0.31	discharge = $729.607 \times \text{stage}^{6.124}$
0.31–0.73	discharge = $11.730 \times \text{stage}^{2.597}$
0.73–1.82	discharge = $11.897 \times \text{stage}^{2.641}$
1.82–2.73	discharge = $10.067 \times \text{stage}^{2.920}$

Table 4.1: Austin Creek rating curves for WY2019 (October 1, 2018-September 30, 2019); equations generated by Aquarius software (Aquatic Informatics, 2014).

Stage Height (ft)	Discharge Equations
1.48–1.90	discharge = $0.000485 \times \text{stage}^{13.023}$
1.90–2.46	discharge = $0.029 \times \text{stage}^{6.632}$
2.46–3.08	discharge = $0.036 \times \text{stage}^{6.412}$
3.08–3.89	discharge = $0.344 \times \text{stage}^{4.398}$
3.89–5.22	discharge = $1.500 \times \text{stage}^{3.315}$

Table 4.2: Smith Creek rating curves for WY2019 (October 1, 2018-September 30, 2019); equations generated by Aquarius software (Aquatic Informatics, 2014).

<i>Austin Creek</i>		<i>Euclid Creek</i>	
Event	Duration	Event	Duration
# 18	19:00 Nov 13 to 05:30 Nov 15, 2018	# 1	19:30 Nov 1 to 02:30 Nov 2, 2018
# 19	17:00 Oct 17 to 07:30 Nov 15, 2019	# 2	19:00 Nov 13 to 14:00 Nov 14, 2018
# 20	10:00 Oct 21 to 06:00 Oct 23, 2019	# 3	20:45 Nov 26 to 18:45 Nov 27, 2018
# 21	15:00 Dec 12 to 05:00 Dec 14, 2019	# 4	10:00 Dec 11 to 01:00 Dec 12, 2018
		# 5	15:00 Jan 22 to 11:00 Jan 23, 2019
		# 6	19:00 Nov 18 to 09:00 Nov 19, 2019
		# 7	01:00 Dec 13 to 13:00 Dec 13, 2019
<i>Silver Beach Creek</i>			
Event	Duration		
# 40	23:00 Nov 1 to 07:00 Nov 2, 2018		
# 41	21:00 Nov 26 to 18:00 Nov 27, 2018		
# 42	17:00 Oct 17 to 11:00 Oct 18, 2019		
# 43	10:00 Oct 21 to 10:00 Oct 22, 2019		
# 44	16:30 Nov 18 to 09:00 Nov 19, 2019		
# 45	17:30 Dec 19 to 05:30 Dec 22, 2019		

Table 4.3: Summary of storm event sampling dates for Austin, Euclid, and Silver Beach Creeks. Austin Creek Events 1–17 and Silver Beach Creek Events 1–39 were discussed in earlier reports (Section 5.2, page 87).




Figure 4.1: Austin Creek hydrograph for WY2019 (October 1, 2018–September 30, 2019). Data were recorded at 15 minute intervals.




Figure 4.2: Smith Creek hydrograph for WY2019 (October 1, 2018–September 30, 2019). Data were recorded at 15 minute intervals.




Figure 4.3: Aquarius rating curve for Austin Creek. The triangles (Δ) show the fitted rating curve for WY2019. The circles show data collected in WY2019 (\bullet), WY2018 (\circ), WY2017 (\circ).




Figure 4.4: Aquarius rating curve for Smith Creek. The triangles (Δ) show the fitted rating curve for WY2019. The circles show data collected in WY2019 (\bullet), WY2018 (\circ), WY2017 (\circ). The red circles (\bullet) show data collected prior to WY2017 that were used for the rating curve because they help define the high end of the rating curve.

5 References and Related Reports

5.1 Cited References

- Aquatic Informatics. 2014. AQUARIUS rating curve software. Aquatic Informatics, Vancouver, British Columbia, Canada.
- APHA. 2017. Standard Methods for the Examination of Water and Wastewater, 23rd Edition. American Public Health Association, American Water Works Association, and Water Environment Federation, Washington, DC.
- Ashurst, S. 2003. Microcosm study of the accumulation of benzo(a)pyrene by Lake Whatcom phytoplankton. M. S. thesis, Huxley College of Environmental Studies, Western Washington University, Bellingham, WA.
- Baribeau, H., S. Krasner, R. Chinn, and P. Singer. 2005. Impact of biomass on the stability of HAAs and THMs in a simulated distribution system. *J. Amer. Water Works Assoc.* 97:69–81
- Bittner, C. W. 1993. The response of Lake Whatcom bacterioplankton to nutrient enrichment. M. S. thesis, Huxley College of Environmental Studies, Western Washington University, Bellingham, WA.
- Deacon, J. 2015. Determining biologically available phosphorus in storm water entering Lake Whatcom, WA using the dual culture diffusion apparatus. M. S. thesis, Huxley College of Environmental Studies, Western Washington University, Bellingham, WA.
- Groce, S. 2011. Soils as a Source of Bioavailable Phosphorus in the Lake Whatcom Watershed. M. S. thesis, Huxley College of the Environment, Western Washington University, Bellingham, WA.
- Granéli, E. and J. T. Turner (Eds). 2006. *Ecology of Harmful Algae*. Springer-Verlag, Berlin, Germany.
- Johengen, T., G. Smith, D. Schar, H. Purcel, D. Loewensteiner, Z. Epperson, M. Tamburri, G. Meadows, S. Green, F. Yousef, J. Anderson. 2016. Performance verification statement for Hach Hydrolab DS5X and HL4 dissolved oxygen sensors. Alliance for Coastal Technologies, Alliance for

Coastal Technologies, ACT VS16-05. DOI: <http://dx.doi.org/10.25607/OBP-298>.

- Liang, C-W. 1994. Impact of Soil and Phosphorus Enrichment on Lake Whatcom Periphytic Algae. M. S. thesis, Huxley College of the Environment, Western Washington University, Bellingham, WA.
- Lind, O. T. 1985. Handbook of Common Methods in Limnology, 2nd Edition. Kendall/Hunt Publishing Co., Dubuque, IA.
- Matthews, R. A. and E. DeLuna, 2008. Metalimnetic oxygen and ammonium maxima in Lake Whatcom, Washington (USA). Northwest Science 82:18–29.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, K. Beeler, and G. B. Matthews. 2015. Lake Whatcom Monitoring Project, 2013/2014 Final Report, February 26, 2015. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. 2012. Lake Whatcom Monitoring Project, 2010/2011 Final Report, February 24, 2012. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. J. Mitchell, and G. B. Matthews. 2008. Lake Whatcom Monitoring Project 2006–2007 Final Report. Final Report prepared for the City of Bellingham Public Works Department, April, 2008, Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. J. Mitchell, and G. B. Matthews. 2005. Lake Whatcom Monitoring Project 2003–2004 Final Report. Final Report prepared for the City of Bellingham Public Works Department, March, 2005, Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. J. Mitchell, and G. B. Matthews. 2004. Lake Whatcom Monitoring Project 2002–2003 Final Report. Final Report prepared for the City of Bellingham Public Works Department, March, 2004, Bellingham, WA.
- Matthews, R., M. Hilles, and G. Pelletier. 2002a. Determining trophic state in Lake Whatcom, Washington (USA), a soft water lake exhibiting seasonal nitrogen limitation. *Hydrobiologia* 468:107–121.

- Matthews, R. A., M. Hilles, J. Vandersypen, R. J. Mitchell, and G. B. Matthews. 2002b. Lake Whatcom Monitoring Project 2000–2001 Final Report. Final Report prepared for the City of Bellingham Public Works Department, March, 2002, Bellingham, WA.
- McDonald, K. R. 1994. Nutrient limitation of phytoplankton in Lake Whatcom. M. S. thesis, Huxley College of Environmental Studies, Western Washington University, Bellingham, WA.
- Mitchell, R., G. Gabrisch, and R. Matthews. 2010. Lake Whatcom Bathymetry and Morphology. Report prepared for the City of Bellingham Public Works Department, December 2, 2010, Bellingham, WA.
- Oliver, S. K., S. M. Colling, P. A. Soranno, T. Wagner, E. H. Stanley, J. R. Jones, C. A. Stow, and N. R. Lottig. 2017. Unexpected stasis in a changing world: lake nutrient and chlorophyll trends since 1990. *Global Change Biology* 23(12): 5455–5467.
- Pelletier, G. 1998. Dissolved oxygen in Lake Whatcom. Trend in the depletion of hypolimnetic oxygen in basin I, 1983–1997. Washington State Department of Ecology Report #98–313, Olympia, WA.
- Potter, B. and F. Wimsatt. 2009. Method 415.3, Rev. 1.2: Determination of Total Organic Carbon and Specific UV Absorbance at 254 nm in Source Water and Drinking Water. U. S. Environmental Protection Agency, Washington, DC.
- Rantz, S.E., et al. (1982). Measurement and Computation of Streamflow: Volume 1. Measurement of Stage and Discharge. Geological Survey Water-Supply Paper #2175, U. S. Government Printing Office, Washington, D. C.
- Rogora, M., S. Arisci, and A. Marchetto. 2012. The role of nitrogen deposition in the recent nitrate decline in lakes and rivers in Northern Italy. *Science of the Total Environment* 417–418: 214–223.
- Sickman, J. O., J. M. Melack, and D. W. Clow. 2003. Evidence for nutrient enrichment of high-elevation lakes in the Sierra Nevada, California. *Limnol. Oceanogr.* 48(5):1885–1892
- Sung, W., B. Reilly-Matthews, D. K. O’Day, and K. Horrigan. 2000. Modeling DBP Formation. *J. Amer. Water Works Assoc.* 92:5–53.

- Waller, K., D. Driscoll, J. Lynch, D. Newcomb, and K. Roy. 2012. Long-term recovery of lakes in the Adirondack region of New York to decreases in acid deposition. *Atmospheric Environment* 46:56–64.
- Wetzel, R. G. 2001. *Limnology*, Third Edition. Academic Press, San Diego, CA.
- WOW. 2004. Water on the Web - Monitoring Minnesota Lakes on the Internet and Training Water Science Technicians for the Future - A National On-line Curriculum using Advanced Technologies and Real-Time Data (<http://WaterOnTheWeb.org>). Authors: Munson, B., R. Axler, C. Hagley, G. Host, G. Merrick, and C. Richards. University of Minnesota-Duluth, Duluth, MN 55812.
- YSI. 2017. EXO User Manual, Revision G, April 2017. YSI Incorporated, Yellow Springs, OH.

5.2 Related Reports

The following is a list of annual reports and special project reports produced by the Institute for Watershed Studies since 1987 as part of the Lake Whatcom monitoring program sponsored by the City of Bellingham and Western Washington University. Many of the reports are available online at www.wwu.edu/iws (follow links to the Lake Whatcom project under Lake Studies); older reports are available in the IWS library and through the city of Bellingham Public Works Department. This list does not include research reports, student projects, or publications that were not prepared specifically for the City of Bellingham. Contact IWS for information about additional Lake Whatcom publications.

Annual monitoring reports:

- Matthews, R. A., M. Hilles, J. Pickins, R. Mitchell, and G. B. Matthews. 2019. Lake Whatcom Monitoring Project, 2017/2018 Final Report, February 26, 2019. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Pickins, R. Mitchell, K. Beeler, and G. B. Matthews. 2018. Lake Whatcom Monitoring Project, 2016/2017 Final Report, February 23, 2018. Report to the City of Bellingham, WA. 0
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, K. Beeler, and G. B. Matthews. 2017. Lake Whatcom Monitoring Project, 2015/2016 Final Report, February 21, 2017. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, K. Beeler, and G. B. Matthews. 2016. Lake Whatcom Monitoring Project, 2014/2015 Final Report, February 23, 2016. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, K. Beeler, and G. B. Matthews. 2015. Lake Whatcom Monitoring Project, 2013/2014 Final Report, February 26, 2015. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. 2014. Lake Whatcom Monitoring Project, 2012/2013 Final Report, March 6, 2014. Report to the City of Bellingham, WA.

- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. 2013. Lake Whatcom Monitoring Project, 2011/2012 Final Report, March 8, 2013. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. 2012. Lake Whatcom Monitoring Project, 2010/2011 Final Report, February 24, 2012. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2009/2010 Final Report, March 1, 2011. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2008/2009 Final Report, March 10, 2010. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2007/2008 Final Report, March 19, 2009. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2006/2007 Final Report, April 2, 2008. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2005/2006 Final Report, April 11, 2007. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2004/2005 Final Report, March 30, 2006. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2003/2004 Final Report, March 15, 2005. Report to the City of Bellingham, WA.
- Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2002/2003 Final Report, April 5, 2004. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2001/2002 Final Report, April 21, 2003. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 2000/2001 Final Report, March 15, 2002. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 1999/2000 Final Report, March 23, 2001. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles, J. Vandersypen, R. Mitchell, and G. B. Matthews. Lake Whatcom Monitoring Project, 1998/99 Final Report, March 15, 2000. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles and G. B. Matthews. Lake Whatcom Monitoring Project, 1997/98 Final Report, April 12, 1999. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles and G. B. Matthews. Lake Whatcom Monitoring Project, 1996/97 Final Report, February 10, 1998. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles and G. B. Matthews. Lake Whatcom Monitoring Project, 1995/96 Final Report, March 24, 1997. Report to the City of Bellingham, WA.

Matthews, R. A., M. Hilles and G. B. Matthews. Lake Whatcom Monitoring Project, 1994/95 Final Report, February 9, 1996. Report to the City of Bellingham, WA.

Matthews, R. A. and G. B. Matthews. Lake Whatcom Monitoring Project, 1993–1994 Final Report, March 2, 1995. Report to the City of Bellingham, WA.

Matthews, R. and G. Matthews. Lake Whatcom Monitoring Project, 1992–1993 Final Report, January 31, 1994. Report to the City of Bellingham, WA.

Matthews, R. and G. Matthews. Lake Whatcom Monitoring Project, 1991–1992 Final Report, March 19, 1993. Report to the City of Bellingham, WA.

Rector, J. M. and R. A. Matthews. Lake Whatcom Monitoring Program, August 1987 Final Report. Institute for Watershed Studies Report, Western Washington University, Bellingham, WA.

Other Lake Whatcom reports:

Matthews, R. A., M. Hilles and J. Vandersypen. Austin Creek and Beaver Creek Sampling Project, October 11, 2005. Report to the City of Bellingham, WA.

Matthews, R. A. Relationship between Drinking Water Treatment Chemical Usage and Lake Whatcom water Quality and Algal Data, October 4, 2004. Report to the City of Bellingham, WA.

Matthews, R. A. Strawberry Sill Water Quality Analysis, March 19, 2004. Report to the City of Bellingham, WA.

Matthews, R. A., M. Saunders, M A. Hilles, and J. Vandersypen. Park Place Wet Pond Monitoring Project, 1994–2000 Summary Report, February 2, 2001. Report to the City of Bellingham, WA.

Carpenter, M. R., C. A. Suczek, and R. A. Matthews. Mirror Lake Sedimentation Study Summary Report, February, 1992. Report to the City of Bellingham, WA.

Walker, S., R. Matthews, and G. Matthews. Lake Whatcom Storm Runoff Project, Final Report, January 13, 1992. Report to the City of Bellingham, WA.

Creahan, K., T. Loranger, B. Gall, D. Brakke, and R. Matthews. Lake Whatcom Watershed Management Plan, December, 1986, revised July, 1987. Institute for Watershed Studies Report, Western Washington University, Bellingham, WA.

A Site Descriptions

Figures A1–A2 (pages 95–96) show the locations of the current monitoring sites and Table A1 (page 94) lists the approximate GPS coordinates for the lake and creek sites. All site descriptions, including text descriptions and GPS coordinates, are approximate. For detailed information about sampling locations, contact IWS.

A.1 Lake Whatcom Monitoring Sites

Site 1 is located in the north central portion of basin 1 along a straight line from the Bloedel Donovan boat launch to the house located at 171 E. North Shore Rd. The depth at Site 1 should be at least 25 meters; samples are collected from the surface to 20 m.

Site 2 is located in the south central portion of basin 2 just west of the intersection of a line joining the boat house at 73 Strawberry Point and the point of Geneva sill. Samples are collected from the surface to 20 m.

The **Intake Site** location is omitted from this report at the City's request.

Site 3 is located in the northern portion of basin 3, mid-basin just north of a line between the old railroad bridge and Lakewood. The depth at Site 3 should be at least 80 m; samples are collected from the surface to 80 m.

Site 4 is located in the southern portion of basin 3, mid-basin, and just north of South Bay. The depth at Site 4 should be at least 90 m; samples are collected from the surface to 90 m.

A.2 Tributary Monitoring Sites

Anderson Creek samples are collected 15 m upstream from South Bay Rd. Water samples and discharge measurements are collected upstream from the bridge. The Anderson Creek hydrograph²⁵ is mounted in the stilling well on the east side of

²⁵This hydrograph is no longer maintained by IWS; data are available on the USGS web site at http://waterdata.usgs.gov/nwis/inventory?agency_code=USGS&site_no=12201950.

Anderson Creek, directly adjacent to the bridge over Anderson Creek (South Bay Rd.), approximately 0.5 km from the mouth of the creek.

The **Austin Creek** hydrograph gauge and sampling site is located approximately 15 m downstream from Lake Whatcom Blvd. From October 2004 through September 2006, three additional sampling sites were sampled in the Austin Creek watershed, so for clarification, the gauged site has been renamed **Lower Austin Creek**.

Blue Canyon Creek samples are collected downstream from the culvert under Blue Canyon Rd. in the second of three small streams that cross the road. This site can be difficult to locate and may be dry or have minimal flow during drought conditions. During low flow conditions, samples are collected, if possible, approx. 7 m upstream from the road crossing.

Brannian Creek samples are collected approximately 40 m downstream from South Bay Rd. near the USGS hydrograph gauge. This site was added in October 2004 as part of the monthly 2004–2006 creek monitoring project.

Carpenter Creek samples are collected approximately 7 m upstream from North Shore Dr. near the USGS hydrograph gauge. This site was added in October 2004 as part of the monthly 2004–2006 creek monitoring project.

Euclid Ave. samples are collected from a small tributary off Euclid Avenue near the USGS hydrograph gauge. The site was added in October 2004 as part of the monthly 2004–2006 creek monitoring project.

Millwheel Creek samples are collected approximately 8 m upstream from Flynn St. near the USGS hydrograph gauge. The creek is unnamed on most topographic maps, but has been called “Millwheel Creek” by residents of the watershed due to its proximity to the old mill pond. This site was added in October 2004 as part of the monthly 2004–2006 creek monitoring project.

Olsen Creek samples are collected upstream from North Shore Dr., approximately 3 meters upstream from the bridge. This site was added in October 2004 as part of the 2004–2006 monthly creek monitoring project.

Park Place samples are collected from the storm drain that empties into Lake Whatcom at Park Place Ln. Samples from this site include outlet flow from the Park Place storm water treatment facility.

Silver Beach Creek samples are collected approximately 75 m upstream from the culvert under North Shore Rd., just upstream from the USGS hydrograph gauge.

The **Smith Creek** hydrograph is mounted on the south wall of a sandstone bluff directly underneath the bridge over Smith Creek (North Shore Rd.) approximately 1 km upstream from the mouth of the creek. Water samples are collected at the gaging station approximately 15 m downstream from North Shore Dr.

Whatcom Creek samples are collected approximately 2 m downstream from the foot bridge below the Lake Whatcom outlet spillway. This site was added in October 2004 as part of the monthly 2004–2006 creek monitoring project.

A.3 Storm Water Monitoring Sites

The 2018–2019 storm water monitoring program focused on collecting storm runoff data from Austin, Euclid, and Silver Beach Creeks. Austin Creek samples are collected approximately 15 m downstream from Lake Whatcom Blvd. Euclid Creek samples are collected from a small tributary located off Euclid Avenue near the USGS hydrograph gauge. Silver Beach Creek samples are collected approximately 75 m upstream from the culvert under North Shore Rd., just upstream from the USGS hydrograph gauge. For information about other storm water sites that have been monitored by IWS, refer to the annual reports listed in Section 5.2 (page 87).

Lake Sites	Latitude (°N)	Longitude (°W)
Site 1	48.760	-122.411
Intake	(GPS omitted)	
Site 2	48.743	-122.382
Site 3	48.738	-122.336
Site 4	48.695	-122.304

Tributary/Stormwater Sites	Latitude (°N)	Longitude (°W)
Anderson	48.673	-122.268
Austin (lower)	48.713	-122.331
Blue Canyon	48.685	-122.283
Brannian	48.669	-122.279
Carpenter	48.754	-122.354
Euclid	48.748	-122.410
Millwheel	48.755	-122.416
Olsen	48.751	-122.354
Park Place	48.769	-122.409
Silver Beach	48.769	-122.407
Smith	48.732	-122.309
Whatcom	48.757	-122.422

Table A1: Approximate GPS coordinates for Lake Whatcom sampling sites.




Figure A1: Lake Whatcom lake sampling sites. Basemap created using data from Western Washington University, Skagit County, the Nooksack Tribe, and the City of Bellingham.




Figure A2: Lake Whatcom tributary and storm water sampling sites. Basemap created using data from Western Washington University, Skagit County, the Nooksack Tribe, and the City of Bellingham.

B Long-Term Water Quality Figures

The current and historic Lake Whatcom water quality data are plotted on the following pages. Detection limits and abbreviations for each parameter are listed in Table 2.1 (page 17).

The historic detection limits for each parameter were estimated based on an analysis of historic detection ranges, instrument limitations, and analyst judgment on the lowest repeatable concentration for each test. Over time, some analytical techniques have improved so that current detection limits are lower than the historic limits listed in Table 2.1, page 17). Because the Lake Whatcom data set includes long-term monitoring data that have been collected using a variety of analytical techniques, this report sets conservative historic detection limits to allow comparisons between all years.

In the Lake Whatcom report, unless indicated, no data substitutions are used for below detection values (“bdl” data). Instead, we identify summary statistics that include bdl values, and, if appropriate, discuss the implications of including these values in the analysis.

Because of the length of the data record, many of the figures reflect trends related to improvements in analytical techniques over time, and introduction of increasingly sensitive field equipment (see, for example, Figures B66–B70, pages 165–169, which show the effect of using increasingly sensitive conductivity probes). These changes generally result in a reduction in analytical variability, and sometimes result in lower detection limits.

B.1 Monthly YSI Profiles




Figure B1: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, October 4, 2018.




Figure B2: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, October 4, 2018.




Figure B3: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, October 4, 2018.




Figure B4: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, October 2, 2018.




Figure B5: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, October 2, 2018.




Figure B6: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, November 8, 2018.




Figure B7: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, November 8, 2018.




Figure B8: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, November 8, 2018.




Figure B9: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, November 6, 2018.




Figure B10: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, November 6, 2018.




Figure B11: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, December 6, 2018.




Figure B12: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, December 6, 2018.




Figure B13: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, December 6, 2018.




Figure B14: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, December 4, 2018.




Figure B15: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, December 4, 2018.




Figure B16: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, February 15, 2019.




Figure B17: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, February 15, 2019.




Figure B18: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, February 15, 2019.




Figure B19: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, February 15, 2019.




Figure B20: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, February 15, 2019.




Figure B21: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, April 16, 2019.




Figure B22: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, April 16, 2019.




Figure B23: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, April 16, 2019.




Figure B24: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, April 11, 2019.




Figure B25: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, April 9, 2019.




Figure B26: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, May 9, 2019.




Figure B27: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, May 9, 2019.




Figure B28: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, May 9, 2019.




Figure B29: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, May 7, 2019.




Figure B30: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, May 7, 2019.




Figure B31: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, June 6, 2019.




Figure B32: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, June 6, 2019.




Figure B33: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, June 6, 2019.




Figure B34: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, June 10, 2019.




Figure B35: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, June 10, 2019.




Figure B36: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, July 11, 2019.




Figure B37: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, July 11, 2019.




Figure B38: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, July 11, 2019.




Figure B39: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, July 9, 2019.




Figure B40: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, July 9, 2019.




Figure B41: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, August 8, 2019.




Figure B42: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, August 8, 2019.




Figure B43: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, August 8, 2019.




Figure B44: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, August 6, 2019. The 80 meter sample from Site 3 has been omitted because it was collected too close to the lake bottom and may not reflect water column conditions.




Figure B45: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, August 6, 2019.




Figure B46: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 1, September 10, 2019.




Figure B47: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 2, September 10, 2019.




Figure B48: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for the Intake, September 10, 2019.




Figure B49: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 3, September 10, 2019. The 80 meter sample from Site 3 has been omitted because it was collected too close to the lake bottom and may not reflect water column conditions.




Figure B50: Lake Whatcom water column profiles showing temperature, pH, conductivity, and dissolved oxygen for Site 4, September 3, 2019.

B.2 Long-term YSI/Hydrolab Data (1988-present)




Figure B51: Lake Whatcom historic temperature data for Site 1.




Figure B52: Lake Whatcom historic temperature data for Site 2.




Figure B53: Lake Whatcom historic temperature data for the Intake.




Figure B54: Lake Whatcom historic temperature data for Site 3.




Figure B55: Lake Whatcom historic temperature data for Site 4.




Figure B56: Lake Whatcom historic dissolved oxygen data for Site 1.




Figure B57: Lake Whatcom historic dissolved oxygen data for Site 2.




Figure B58: Lake Whatcom historic dissolved oxygen data for the Intake. See discussion of the low dissolved oxygen value in Matthews et al. (2014).




Figure B59: Lake Whatcom historic dissolved oxygen data for Site 3.




Figure B60: Lake Whatcom historic dissolved oxygen data for Site 4.




Figure B61: Lake Whatcom historic pH data for Site 1.




Figure B62: Lake Whatcom historic pH data for Site 2.




Figure B63: Lake Whatcom historic pH data for the Intake.




Figure B64: Lake Whatcom historic pH data for Site 3.




Figure B65: Lake Whatcom historic pH data for Site 4.




Figure B66: Lake Whatcom historic conductivity data for Site 1. The decreasing conductivity trend is the result of changing to more sensitive equipment.




Figure B67: Lake Whatcom historic conductivity data for Site 2. The decreasing conductivity trend is the result of changing to more sensitive equipment.




Figure B68: Lake Whatcom historic conductivity data for the Intake. The decreasing conductivity trend is the result of changing to more sensitive equipment.




Figure B69: Lake Whatcom historic conductivity data for Site 3. The decreasing conductivity trend is the result of changing to more sensitive equipment.




Figure B70: Lake Whatcom historic conductivity data for Site 4. The decreasing conductivity trend is the result of changing to more sensitive equipment.

B.3 Long-term Water Quality Data (1988-present)




Figure B71: Lake Whatcom alkalinity data for Site 1.




Figure B72: Lake Whatcom alkalinity data for Site 2.




Figure B73: Lake Whatcom alkalinity data for the Intake site.




Figure B74: Lake Whatcom alkalinity data for Site 3.




Figure B75: Lake Whatcom alkalinity data for Site 4.




Figure B76: Lake Whatcom turbidity data for Site 1.




Figure B77: Lake Whatcom turbidity data for Site 2.




Figure B78: Lake Whatcom turbidity data for the Intake site.




Figure B79: Lake Whatcom turbidity data for Site 3.




Figure B80: Lake Whatcom turbidity data for Site 4.




Figure B81: Lake Whatcom ammonium data for Site 1.




Figure B82: Lake Whatcom ammonium data for Site 2.




Figure B83: Lake Whatcom ammonium data for the Intake site.




Figure B84: Lake Whatcom ammonium data for Site 3.




Figure B85: Lake Whatcom ammonium data for Site 4.




Figure B86: Lake Whatcom nitrate/nitrite data for Site 1.




Figure B87: Lake Whatcom nitrate/nitrite data for Site 2.




Figure B88: Lake Whatcom nitrate/nitrite data for the Intake site.




Figure B89: Lake Whatcom nitrate/nitrite data for Site 3.




Figure B90: Lake Whatcom nitrate/nitrite data for Site 4.




Figure B91: Lake Whatcom total nitrogen data for Site 1.




Figure B92: Lake Whatcom total nitrogen data for Site 2.




Figure B93: Lake Whatcom total nitrogen data for the Intake site.




Figure B94: Lake Whatcom total nitrogen data for Site 3.




Figure B95: Lake Whatcom total nitrogen data for Site 4.




Figure B96: Lake Whatcom soluble phosphate data for Site 1.




Figure B97: Lake Whatcom soluble phosphate data for Site 2.




Figure B98: Lake Whatcom soluble phosphate data for the Intake site.




Figure B99: Lake Whatcom soluble phosphate data for Site 3.




Figure B100: Lake Whatcom soluble phosphate data for Site 4.




Figure B101: Lake Whatcom total phosphorus data for Site 1.




Figure B102: Lake Whatcom total phosphorus data for Site 2.




Figure B103: Lake Whatcom total phosphorus data for the Intake site.




Figure B104: Lake Whatcom total phosphorus data for Site 3.




Figure B105: Lake Whatcom total phosphorus data for Site 4.




Figure B106: Lake Whatcom chlorophyll data for Site 1.




Figure B107: Lake Whatcom chlorophyll data for Site 2.




Figure B108: Lake Whatcom chlorophyll data for the Intake site.




Figure B109: Lake Whatcom chlorophyll data for Site 3.




Figure B110: Lake Whatcom chlorophyll data for Site 4.




Figure B111: Lake Whatcom Secchi depths for Site 1.




Figure B112: Lake Whatcom Secchi depths for Site 2.




Figure B113: Lake Whatcom Secchi depths for the Intake site.




Figure B114: Lake Whatcom Secchi depths for Site 3.




Figure B115: Lake Whatcom Secchi depths for Site 4.




Figure B116: Lake Whatcom fecal coliform data for Site 1.




Figure B117: Lake Whatcom fecal coliform data for Site 2.




Figure B120: Lake Whatcom fecal coliform data for Site 4.




Figure B121: Lake Whatcom plankton data for Site 1.




Figure B122: Lake Whatcom plankton data for Site 2.




Figure B123: Lake Whatcom plankton data for the Intake Site.




Figure B124: Lake Whatcom plankton data for Site 3.




Figure B125: Lake Whatcom plankton data for Site 4.




Figure B126: Lake Whatcom plankton data for Site 1, with Chrysophyta omitted to show remaining plankton groups.




Figure B127: Lake Whatcom plankton data for Site 2, with Chrysophyta omitted to show remaining plankton groups.




Figure B128: Lake Whatcom plankton data for the Intake Site, with Chrysophyta omitted to show remaining plankton groups.




Figure B129: Lake Whatcom plankton data for Site 3, with Chrysophyta omitted to show remaining plankton groups.




Figure B130: Lake Whatcom plankton data for Site 4, with Chrysophyta omitted to show remaining plankton groups.

B.4 Lake Whatcom Tributary Data (2004-present)

The figures in this appendix include the monthly or biannual baseline data collected from 2004 through the current monitoring period. Each figure includes a dashed (blue) horizontal line that shows the median value for Smith Creek and a solid (red) horizontal line that shows the median value for each creek. Smith Creek was chosen as a reference because it is a major tributary to the lake and has a history of being relatively unpolluted. The figures were scaled to include all but extreme outliers; off-scale outliers are listed in Table [B1](#) (page [232](#)).

Site	Date	Parameter	Concentration
Anderson	January 10, 2006	Total susp. solids	168.8 mg/L
Austin	January 10, 2006	Total susp. solids	166.5 mg/L
Brannian	March 3, 2014	Total phosphorus	349.8 $\mu\text{g-P/L}$
	March 3, 2014	Total susp. solids	328.5 mg/L
Millwheel	February 8, 2005	Ammonium	569.4 $\mu\text{g-N/L}$
	February 8, 2005	Soluble phosphate	116.5 $\mu\text{g-P/L}$
	September 14, 2010	Total phosphorus	217.2 $\mu\text{g-P/L}$
	July 11, 2011	Ammonium	291.7 $\mu\text{g-N/L}$
	October 12, 2011	Total phosphorus	521.8 $\mu\text{g-P/L}$
	September 12, 2012	Ammonium	837.7 $\mu\text{g-N/L}$
	September 12, 2012	Total phosphorus	452.2 $\mu\text{g-P/L}$
	July 8, 2014	Total phosphorus	788.2 $\mu\text{g-P/L}$
	July 8, 2014	Soluble phosphate	165.1 $\mu\text{g-P/L}$
	July 8, 2014	Ammonium	1956.4 $\mu\text{g-N/L}$
	September 9, 2014	Total phosphorus	263.5 $\mu\text{g-P/L}$
	October 9, 2018	Total phosphorus	1,342 $\mu\text{g-P/L}$
Olsen	January 10, 2006	Total susp. solids	166.9 mg/L
Park Place	August 1, 2006	F. coliforms	18,000 cfu/100 mL
	July 18, 2017	F. coliforms	19,000 cfu/100 mL
	June 12, 2018	F. coliforms	6,200 cfu/100 mL
	May 14, 2019	Ammonium	693.3 $\mu\text{g-N/L}$
	May 14, 2019	Soluble phosphate	111.8 $\mu\text{g-P/L}$
Silver Beach	October 10, 2005	F. coliforms	5,800 cfu/100 mL
	August 1, 2006	F. coliforms	12,000 cfu/100 mL
	July 17, 2007	F. coliforms	5,300 cfu/100 mL
	July 8, 2014	F. coliforms	5,700 cfu/100 mL

Table B1: List of outliers omitted from Figures B131–B169 to preserve scale.




Figure B131: Temperature data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B132: Temperature data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B133: Temperature data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B134: Dissolved oxygen data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B135: Dissolved oxygen data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B136: Dissolved oxygen data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B137: Tributary pH data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B138: Tributary pH data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B139: Tributary pH data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B140: Conductivity data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B141: Conductivity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B142: Conductivity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B143: Alkalinity data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B144: Alkalinity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B145: Alkalinity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B146: Total suspended solids data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B147: Total suspended solids data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B148: Total suspended solids data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B149: Turbidity data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B150: Turbidity data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B151: Turbidity data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B152: Ammonium data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B153: Ammonium data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B154: Ammonium data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B155: Nitrate/nitrite data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B 156: Nitrate/nitrite data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B157: Nitrate/nitrite data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B158: Total nitrogen data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B159: Total nitrogen data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B160: Total nitrogen data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B161: Soluble phosphate data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B162: Soluble phosphate data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B163: Soluble phosphate data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B164: Total phosphorus data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B165: Total phosphorus data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B166: Total phosphorus data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B167: Fecal coliform data for Anderson, Austin, Smith, and Whatcom Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B168: Fecal coliform data for Blue Canyon, Brannian, Carpenter, and Olsen Creeks. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.




Figure B169: Fecal coliform data for Euclid, Millwheel, and Silver Beach Creeks and the Park Place drain. Dashed (blue) horizontal reference line shows the median value for Smith Creek; solid (red) horizontal reference line shows the median value for each creek.

C Quality Control

C.1 Performance Evaluation Reports

In order to maintain a high degree of accuracy and confidence in the water quality data all personnel associated with this project were trained according to standard operating procedures for the methods listed in Table 2.1 (page 17). Single-blind quality control tests were conducted as part of the IWS laboratory certification process (Table C1).

C.2 Laboratory Duplicates, Spikes, and Check Standards

Ten percent of all samples analyzed in the laboratory were duplicated to measure analytical precision. Sample matrix spikes were analyzed during each analytical run to evaluate analyte recovery for the nutrient analyses (ammonium, nitrate/nitrite, total nitrogen, soluble reactive phosphate, and total phosphorus). External check standards were analyzed during each analytical run to evaluate measurement precision and accuracy.²⁶ The quality control results for laboratory duplicates, matrix spikes, and check standards are plotted in control charts (Figures C1–C30, pages 274–303).

C.3 Field Duplicates

Ten percent of all samples collected in the field were duplicated to measure sample replication (Figures C31–C48, pages 304–321). Samples collected using field meters (conductivity, dissolved oxygen, and pH) were evaluated using water samples collected from the same depth as the field meter measurement. The absolute mean difference for the field duplicates was calculated as follows:

$$\text{Absolute mean difference} = \frac{\sum |\text{Original Sample} - \text{Duplicate Sample}|}{\text{number of duplicate pairs}}$$

²⁶External check standards are not available for all analytes.

	Reported Value	Assigned Value	Acceptance Limits	Test Result
Specific conductivity ($\mu\text{S}/\text{cm}$ at 25°C)	449	448	403–493	accept
Total alkalinity (mg/L as CaCO_3)	144	145	123–167	accept
Ammonium nitrogen, manual (mg-N/L)	6.90	6.66	5.23–8.10	accept
Ammonium nitrogen, auto (mg-N/L)	6.49	6.66	5.23–8.10	accept
Nitrate/nitrite nitrogen, auto (mg-N/L)	12.8	13.6	11.3–15.7	accept
Nitrite nitrogen, auto (mg-N/L)	2.95	2.93	2.53–3.34	accept
Organic carbon, dissolved (mg/L) [†]	5.09	5.26	4.66–5.79	accept
Organic carbon, total (mg/L) [†]	5.06	5.26	4.21–6.31	accept
Orthophosphate, manual (mg-P/L)	3.20	3.18	2.70–3.66	accept
Orthophosphate, auto (mg-P/L)	3.22	3.18	2.70–3.66	accept
Total phosphorus, manual (mg-P/L)	5.65	5.61	4.65–6.51	accept
Total phosphorus, auto (mg-P/L)	5.87	5.61	4.65–6.51	accept
pH	6.77	6.77	6.57–6.97	accept
Solids, non-filterable (mg/L)	37.6	45.7	35.0–52.7	accept
Turbidity (NTU)	23.7	24.8	20.9–28.9	accept

Table C1: Single-blind quality control results, WP–250 (11/23/2018); all results were within acceptance limits. IWS is applying for certification for total organic carbon analyses; the performance evaluation results ([†]WP–116, 11/29/2018) are reported here.





Figure C1: Alkalinity laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C2: Alkalinity high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C3: Alkalinity low-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C4: Chlorophyll laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C5: Conductivity laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C6: Dissolved oxygen laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C7: Nitrogen (ammonium) laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C8: Nitrogen (ammonium) spike recoveries for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of spike data.





Figure C9: Nitrogen (ammonium) high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C10: Nitrogen (ammonium) low-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C11: Nitrogen (nitrate/nitrite) laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C12: Nitrogen (nitrate/nitrite) spike recoveries for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of spike data.





Figure C13: Nitrogen (nitrate/nitrite) high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C14: Nitrogen (nitrate/nitrite) low-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C15: Nitrogen (total) laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C16: Nitrogen (total) spike recoveries for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of spike data.





Figure C17: Nitrogen (total) high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C18: Nitrogen (total) low-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C19: Laboratory pH duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C20: Phosphorus (soluble reactive phosphate) laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C21: Phosphorus (soluble reactive phosphate) spike recoveries for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of spike data.






Figure C22: Phosphorus (soluble reactive phosphate) high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.







Figure C24: Phosphorus (total) laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C25: Phosphorus (total) spike recoveries for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of spike data.





Figure C26: Phosphorus (total) high-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C27: Phosphorus (total) low-range check standards for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C28: Total suspended solids laboratory duplicates for the Lake Whatcom monitoring program (tributary and storm water samples). Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.





Figure C29: Total suspended solids check standards for the Lake Whatcom monitoring program (tributary and storm water samples). Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of check standard data.





Figure C30: Turbidity laboratory duplicates for the Lake Whatcom monitoring program. Upper/lower acceptance limits (± 2 std. dev. from mean pair difference) and upper/lower warning limits (± 3 std. dev. from mean pair difference) were calculated based on the preceding two years of lab duplicate data.




Figure C31: Alkalinity field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship.




Figure C32: Alkalinity field duplicates for the 2018/2019 Lake Whatcom monitoring program tributary samples). Diagonal reference line shows 1:1 relationship.




Figure C33: Chlorophyll field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship.




Figure C34: Conductivity field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship.




Figure C35: Dissolved oxygen field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship. The labeled outliers were collected when extreme gradients were present. Field meter samples were collected at true depth; Winkler samples were measured in the laboratory from samples collected using a marked line, which will be slightly shallower than true depth. There was a systematic bias between the Winkler and field meter results, with the Winkler results ~ 0.5 mg/L lower than the field meter. This is within typical ranges for Winkler vs. field meter comparisons (Johengen, et al. 2016).




Figure C36: Dissolved oxygen field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship. There was a systematic bias between the Winkler and field meter results, with the Winkler results ~ 0.5 mg/L lower than the field meter. This is within typical ranges for Winkler vs. field meter comparisons (Johengen, et al. 2016).




Figure C37: Nitrogen (ammonium) field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit. The high degree of scatter is due to the low concentrations of the samples.




Figure C38: Nitrogen (ammonium) field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit. The high degree of scatter is due to the low concentrations of the samples.




Figure C39: Nitrogen (nitrate/nitrite) field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C40: Nitrogen (nitrate/nitrite) field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C41: Nitrogen (total) field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship.




Figure C42: Nitrogen (total) field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship.




Figure C43: Field duplicates for pH from the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship. A systematic bias was observed for pH values ≤ 7.0 .




Figure C44: Phosphorus (soluble reactive phosphate) field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C45: Phosphorus (total) field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C46: Phosphorus (total) field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C47: Total suspended solids field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship; horizontal reference line shows current detection limit.




Figure C48: Turbidity field duplicates for the 2018/2019 Lake Whatcom monitoring program (lake samples). Diagonal reference line shows 1:1 relationship.




Figure C49: Turbidity field duplicates for the 2018/2019 Lake Whatcom monitoring program (tributary samples). Diagonal reference line shows 1:1 relationship.

D Lake Whatcom Online Data

The following **readme** file describes the electronic data posted at the IWS web site (www.wvu.edu/iws) and additional data available from IWS. Please contact the Director of the Institute for Watershed Studies if you have questions or trouble accessing the online data.

```
*****  
* README FILE - LAKE WHATCOM ONLINE DATA  
* THIS FILE WAS UPDATED NOVEMBER 10, 2019  
*****  
Most of the Lake Whatcom water quality data are available in  
electronic format at the IWS website (http://www.wvu.edu/iws) or from  
the IWS Director.
```

The historic and current detection limits and abbreviations for each parameter are listed in the annual reports. The historic detection limits for each parameter were estimated based on recommended lower detection ranges, instrument limitations, and analyst judgment on the lowest repeatable concentration for each test. Over time, some analytical techniques have improved so that current detection limits are usually lower than historic detection limits. Because the Lake Whatcom data set includes long-term monitoring data, which have been collected using a variety of analytical techniques, this report sets conservative detection limits to allow comparisons between years.

All files are comma-separated ascii data files. The code "NA" has been entered into all empty cells in the ascii data files to fill in unsampled dates and depths, missing data, etc. Questions about missing data should be directed to the IWS Director.

Unless otherwise indicated, the electronic data files have NOT been censored to flag or otherwise identify below detection and above detection values. As a result, the ascii files may contain negative values due to linear extrapolation of the standards regression curve for below detection data. It is essential that any statistical or analytical results that are generated using these data be reviewed by someone familiar with statistical uncertainty associated with uncensored data.

* ONLINE LAKE DATA FILES:

Hydrolab/YSI data

1988_hl.csv, 1989_hl.csv, 1990_hl.csv, 1991_hl.csv, 1992_hl.csv
 1993_hl.csv, 1994_hl.csv, 1995_hl.csv, 1996_hl.csv, 1997_hl.csv
 1998_hl.csv, 1999_hl.csv, 2000_hl.csv, 2001_hl.csv, 2002_hl.csv
 2003_hl.csv, 2004_hl.csv, 2005_hl.csv, 2006_hl.csv, 2007_hl.csv
 2008_hl.csv, 2009_hl.csv, 2010_hl.csv, 2011_hl.csv, 2012_hl.csv
 2013_hl.csv, 2014_hl.csv, 2015_hl.csv, 2016_hl.csv, 2017_hl.csv
 2018_hl.csv, 2019_hl.csv

Water quality data

1988_wq.csv, 1989_wq.csv, 1990_wq.csv, 1991_wq.csv, 1992_wq.csv
 1993_wq.csv, 1994_wq.csv, 1995_wq.csv, 1996_wq.csv, 1997_wq.csv
 1998_wq.csv, 1999_wq.csv, 2000_wq.csv, 2001_wq.csv, 2002_wq.csv
 2003_wq.csv, 2004_wq.csv, 2005_wq.csv, 2006_wq.csv, 2007_wq.csv
 2008_wq.csv, 2009_wq.csv, 2010_wq.csv, 2011_wq.csv, 2012_wq.csv
 2013_wq.csv, 2014_wq.csv, 2015_wq.csv, 2016_wq.csv, 2017_wq.csv
 2018_wq.csv, 2019_wq.csv

Plankton counts

plankton.csv

The *_hl.csv files include: site, depth (m), month, day, year, temp (temperature, C), pH, cond (conductivity, uS/cm), do (dissolved oxygen, mg/L), lcond (lab conductivity qc, uS/cm), secchi (secchi depth, m).

The *_wq.csv files include: site, depth (m), month, day, year, alk (alkalinity, mg/L as CaCO3), turb (turbidity, NTU), nh3 (ammonium, ug-N/L), tn (total persulfate nitrogen, ug-N/L), nos (nitrate/nitrite, ug-N/L), srp (soluble reactive phosphate, ug-P/L), tp (total persulfate phosphorus, ug-P/L), chl (chlorophyll, ug/L).

The plankton.csv file includes: site, depth (m), month, day, year, zoop (zooplankton, #/L), chry (chrysophyta, #/L), cyan (cyano-bacteria, #/L), chlo (chlorophyta, #/L), pyrr (pyrrophyta, #/L).

* ONLINE HYDROGRAPH DATA FILES:

WY1998.csv, WY1999.csv, WY2000_rev.csv (rev. 3/8/2012), WY2001.csv,
 WY2002.csv, WY2003.csv, WY2004_rev.csv (rev. 6/21/2006), WY2005.csv,
 WY2006.csv, WY2007.csv (rev. July 31, 2008), WY2008.csv, WY2009.csv,

WY2010.csv, WY2011.csv, WY2012.csv, WY2013.csv, WY2014.csv, WY2015.csv
WY2016.csv, WY2017.csv, WY2018.csv, WY2019.csv

The WY*.csv files include: month, day, year, hour, min, sec, ander.g (anderson gauge height, ft), ander.cfs (anderson discharge, cfs), austin.g (austin gauge height, ft), austin.cfs (austin discharge, cfs), smith.g (smith gauge height, ft), smith.cfs (smith discharge, cfs). Anderson Creek hydrograph data were deleted in WY2000_rev.csv due to uncertainty about the gauge height; Anderson Creek data are available for WY1998, WY1999, and WY2001-WY2007. Beginning with WY2002, the variable "time" replaced "hour, min, sec," with time reported daily on a 24-hr basis. Data are reported as Pacific Standard Time without Daylight Saving Time adjustment.

* STORM WATER AND TRIBUTARY DATA FILES

The storm water and tributary data include composite and grab samples from numerous sites in the Lake Whatcom watershed (1994--present), representing a variety of study objectives and sampling intensities over time. The electronic data files are not posted online, but may be obtained by contacting the Institute for Watershed Studies.

* SITE CODES

* ALL FILES - INCLUDES DISCONTINUED SITES AND OFF-LINE DATA

The site codes in the data are as follows:

11 = Lake Whatcom Site 1
21 = Lake Whatcom Intake site
22 = Lake Whatcom Site 2
31 = Lake Whatcom Site 3
32 = Lake Whatcom Site 4
33 = Strawberry Sill site S1
34 = Strawberry Sill site S2
35 = Strawberry Sill site S3

AlabamaVault inlet = Alabama canister vault inlet
AlabamaVault outlet = Alabama canister vault outlet
Brentwood inlet = Brentwood wet pond inlet
Brentwood outlet = Brentwood wet pond outlet
ParkPlace cell1 = Park Place wet pond cell 1
ParkPlace cell2 = Park Place wet pond cell 2
ParkPlace cell3 = Park Place wet pond cell 3
ParkPlace inlet = Park Place wet pond inlet

ParkPlace outlet = Park Place wet pond outlet
Parkstone_swale inlet = Parkstone grass swale inlet
Parkstone_swale outlet = Parkstone grass swale outlet
Parkstone_pond inlet = Parkstone wet pond inlet
Parkstone_pond outlet = Parkstone wet pond outlet
SouthCampus inlet = South Campus storm water facility inlet
SouthCampus outletE = South Campus storm water facility east outlet
SouthCampus outletW = South Campus storm water facility west outlet
Sylvan inlet = Sylvan storm drain inlet
Sylvan outlet = Sylvan storm drain outlet
Wetland outlet = Grace Lane wetland

CW1 = Smith Creek (see alternate code below)
CW2 = Silver Beach Creek (see alternate code below)
CW3 = Park Place drain (see alternate code below)
CW4 = Blue Canyon Creek (see alternate code below)
CW5 = Anderson Creek (see alternate code below)
CW6 = Wildwood Creek (discontinued in 2004)
CW7 = Austin Creek (see alternate code below)

The following tributary site codes were used for the expanded 2004–2006 tributary monitoring project

AND = Anderson Creek (same location as CW5 above)
BEA1 = Austin.Beaver.confluence
AUS = Austin.lower (same location as CW7 above)
BEA2 = Austin.upper
BEA3 = Beaver.upper
BLU = BlueCanyon (same location as CW4 above)
BRA = Brannian
CAR = Carpenter
EUC = Euclid
MIL = Millwheel
OLS = Olsen
PAR = ParkPlace (same location as CW3 above)
SIL = SilverBeach (same location as CW2 above)
SMI = Smith (same location as CW1 above)
WHA = Whatcom

* VERIFICATION PROCESS FOR THE LAKE WHATCOM DATA FILES

During the summer of 1998 the Institute for Watershed Studies began creating an electronic data file that would contain long term data records for Lake Whatcom. These data were to be included with annual Lake Whatcom monitoring reports. This was the first attempt to make a long-term Lake Whatcom data record available to the public. Because these data had been generated using different quality control plans over the years, a comprehensive re-verification process was done.

The re-verification started with printing a copy of the entire data file and checking 5% of all entries against historic laboratory bench sheets and field notebooks. If an error was found, the entire set of values for that analysis were reviewed for the sampling period containing the error. Corrections were noted in the printed copy and entered into the electronic file; all entries were dated and initialed in the archive copy.

Next, all data were plotted and descriptive statistics (e.g., minimum, maximum) were computed to identify outliers and unusual results. All outliers and unusual data were verified against original bench sheets. A summary of decisions pertaining to these data is presented below. All verification actions were entered into the printed copy, dated, and initialed by the IWS director.

The following is a partial list of the changes made to the verified Lake Whatcom data files. For detailed information refer to the data verification archive files in the IWS library.

Specific Deletions: 1) Rows containing only missing values were deleted. 2) All lab conductivity for February 1993 were deleted for cause: meter inadequate for low conductivity readings (borrowed Huxley's student meter). 3) All Hydrolab conductivity from April - December 1993 were deleted for cause: Hydrolab probe slowly lost sensitivity. Probe was replaced and Hydrolab was reconditioned prior to the February 1994 sampling. 4) All 1993 Hydrolab dissolved oxygen data less than or equal to 2.6 mg/L were deleted for cause: Hydrolab probe lost sensitivity at low oxygen concentrations. Probe was replaced and Hydrolab was reconditioned prior to February 1994 sampling. 5) All srp and tp data were deleted (entered as "missing" in 1989) from the July 10, 1989 wq data due to sample contamination in at least three samples. 6) December 2, 1991, Site 3, 0 m conductivity point deleted due to inconsistency with adjacent points. 7) December 15, 1993, Site 4, 80 m lab conductivity point deleted because matching

field conductivity data are absent and point is inconsistent with all other lab conductivity points. 8) November 4, 1991, Site 2, 17-20 m, conductivity points deleted due to evidence of equipment problems related to depth. 9) February 2, 1990, Site 1, 20 m, soluble reactive phosphate and total phosphorus points deleted due to evidence of sample contamination. 10) August 6, 1990, Site 1, 0 m, soluble reactive phosphate and total phosphorus points deleted due to evidence of sample contamination. 11) October 5, 1992, Site 3, 80 m, all data deleted due to evidence of sample contamination in turbidity, ammonium, and total phosphorus results. 12) August 31, 1992, Site 3, 5 m, soluble reactive phosphate and total phosphorus data deleted due to probable coding error. 13) All total Kjeldahl nitrogen data were removed from the historic record. This was not due to errors with the data but rather on-going confusion over which records contained total persulfate nitrogen and which contained total Kjeldahl nitrogen. The current historic record contains only total persulfate nitrogen. Total Kjeldahl nitrogen data were retained in the IWS data base, but not in the long-term Lake Whatcom data files.

* ROUTINE DATA VERIFICATION PROCESS

1994-present: The Lake Whatcom data are verified using a four step method: 1) The results are reviewed as they are generated. Outliers are checked for possible analytical or computational errors. This step is completed by the Laboratory Analyst and IWS Laboratory Supervisor. 2) The results are reviewed monthly or quarterly and sent to the City. Unusual results are identified. This step is completed by the IWS Director. 3) The results are reviewed on an annual basis and discussed in the Lake Whatcom Monitoring Program Final Report. Unusual results are identified, and explained, if possible. This step is completed by the IWS Director, IWS Laboratory Supervisor, and Laboratory Analyst. 4) Single-blind quality control samples, laboratory duplicates, and field duplicates are analyzed as specified in the Lake Whatcom Monitoring Program contract and in the IWS Laboratory Certification requirements. Unusual results that suggest instrumentation or analytical problems are reported to the IWS Director and City. The results from these analyses are summarized in the annual report.

1987-1993: The lake data were reviewed as above except that the IWS Director's responsibilities were delegated to the Principle Investigator in charge of the lake monitoring contract.

Prior to 1987: Data were informally reviewed by the Laboratory Analyst and IWS Director. Laboratory and field duplicates were commonly included as part of the analysis process, but no formal (i.e., written) quality control program was in place. Laboratory logs were maintained for most analyses, so it is possible to verify data against original analytical results. It is also possible to review laboratory quality control results for some analyses.